

ORIGINAL

WELL COMPLETION FORM
WELL HISTORY - DESCRIPTION OF WELL & LEASE

Operator: License # 32309
Name: Presco Western, LLC
Address 5665 FLATIRON PARKWAY
City/State/Zip BOULDER CO 80301
Purchaser: Texon, LP (Oil); One OK (Gas)
Operator Contact Person: Randy M. Verret
Phone (303) 305-1163
Contractor: Name: Trinidad Cheyenne Drilling LP
License: 33375 33784
Wellsite Geologist: Not Applicable

Designate Type of Completion
 New Well Re-Entry Workover
 Oil SWD SIOW Temp. Abd.
 Gas ENHR SIGW
 Dry Other (Core, WSW, Expl., Cathodic, etc.)


If Workover/Reentry: Old Well Info as follows:
Operator: _____
Well Name: _____
Original Comp. Date _____ Original Total Depth _____
 Deepening Re-perf. Conv. to Enhr./SWD
 Plug Back _____ Plug Back Total Depth _____
 Commingled _____ Docket No. _____
 Dual Completion _____ Docket No. _____
 Other (SWD or Enhr?) _____ Docket No. _____
3/1/07 3/11/07 4/17/07
Spud Date or Date Reached TD Completion Date or Recompletion Date

API NO. 15- 055-21936-0000
County Finney
SE - NE - SW - SE Sec. 26 Twp. 26 S. R. 32 E W
904 Feet from S/N (circle one) Line of Section
1,416 Feet from E/W (circle one) Line of Section
Footages Calculated from Nearest Outside Section Corner:
(circle one) NE SE NW SW
Lease Name Duesing Well # 5-026-26-32
Field Name Unnamed
Producing Formation Morrow
Elevation: Ground 2,852.9' Kelley Bushing 2,865
Total Depth 5,275' Plug Back Total Depth 5,254'
Amount of Surface Pipe Set and Cemented at 1,709 Feet
Multiple Stage Cementing Collar Used? Yes No
If yes, show depth set _____ Feet
If Alternate II completion, cement circulated from _____
feet depth to _____ w/ _____ sx cmt.

Drilling Fluid Management Plan ACT INH 7-22-08
(Data must be collected from the Reserve Pit)
Chloride content 4,000 ppm Fluid volume 1,700 bbls
Dewatering method used Air Evaporation RECEIVED
Location of fluid disposal if hauled offsite: KANSAS CORPORATION COMMISSION
Operator Name Not Applicable ACT 29 2007
Lease Name _____ License No. _____
Quarter _____ Sec. _____ Twp. _____ S. R. WICHITA, KS E W
County _____ Docket No. _____

INSTRUCTIONS: An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. Market - Room 2078, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information on side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 for plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.
Signature Randy M. Verret
Title Manager- Business & Regulatory Affairs Date _____
Subscribed and sworn to before me this 26th day of October, 2007.
Notary Public [Signature]
Date Commission Expires 7-28-09 My Commission Expires 07/28/2009



KCC Office Use ONLY
 Letter of Confidentiality Attached
If Denied, Yes Date: _____
 Wireline Log Received
 Geologist Report Received
 UIC Distribution

Operator Name Presco Western, LLC

Lease Name Duesing

Well # 5-026-26-32

Sec. 26 Twp. 26 S.R. 32 East West

County Finney

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all drill stem tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface during test. Attach extra sheet if more space is needed. Attach copy of all Electric Wireline Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken (Attach Additional Sheets.) Yes No

Samples Sent to Geological Survey Yes No

Cores Taken Yes No

Electric Log Run (Submit Copy.) Yes No

List All E.Logs Run:

Dual Induction; Compensated Neutron/SSD & Borehole Compensated Sonic/ITT

Log Formation (Top), Depth and Datums Sample

Name	Top	Datum
Lansing	4,090'	-1,225'
Kansas City	4,458'	-1,593'
Marmaton	4,573'	-1,708'
Morrow	4,901'	-2,036'
St. Louis	5,092'	-2,227'

CASING RECORD New Used

Report all strings set-conductor, surface, intermediate, production, etc.

Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs./Ft.	Setting Depth	Type of Cement	# Sacks Used	Type and Percent Additives
Surface	12-1/4"	8-5/8"	23.5	1,709'	Comm	150	3%CC
					Lite	575	3%CC 1/4 Flo
Production	7-7/8"	5-1/2"	17.5	5,273'	ASC	175	10%Salt/2%Gel

ADDITIONAL CEMENTING/SQUEEZE RECORD

Purpose	Depth Top Bottom	Type of Cement	#Sacks Used	Type and Percent Additives
Perforate				
Protect Casing				
Plug Back-TD				
Plug Off Zone				

Shots Per Foot	PERFORATION RECORD - Bridge Plugs Set/Type Specify Footage of Each Interval Perforated	Acid, Fracture, Shot, Cement Squeeze Record (Amount and Kind of Material Used)	Depth
4	4,309' -4,318' (Lansing)		
4	4,460' -4,470' (Kansas City)	24 bbls. Acid/ 30 bbls. Flush	
4	4,789' -91' & 4,800' -01' (Atoka)	24 bbls. Acid/ 30 bbls. Flush	
4	4,990' -4,995' (Morrow)	24 bbls. Acid/ 30 bbls. Flush	

TUBING RECORD Size N/A Set At Packer At Liner Run Yes No

Date of First, Resumed Production, SWD or Enhr. 4/17/07- Unsuccessful Completion Producing Method Flowing Pumping Gas Lift Other (Explain)

Estimated Production Per 24 Hours Oil N/A Bbls. Gas Mcf Water Bbls. Gas-Oil Ratio Gravity

Disposition of Gas: METHOD OF COMPLETION

Vented Sold Used on Lease Open Hole Perforation Dually Comp. Commingled Other (Specify)

(If vented, submit ACO-18.)

CO. OF COLO. STATE

ALLIED CEMENTING CO., INC. 25291

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:
OAKLEY

DATE <u>3-12-07</u>	SEC. <u>26</u>	TWP. <u>26S</u>	RANGE <u>32W</u>	CALLED OUT	ON LOCATION <u>2:45 AM</u>	JOB START <u>7:00 AM</u>	JOB FINISH <u>8:00 AM</u>
LEASE <u>QUESTING</u>		WELL# <u>5-026</u>	LOCATION <u>GARDEN CITY 153-56-4A-W</u>			COUNTY <u>FENNEY</u>	STATE <u>KS</u>
OLD OR (NEW) (Circle one)							

CONTRACTOR <u>CHEYENNE DRILL RIG #16</u>	OWNER <u>SARNE</u>
TYPE OF JOB <u>PRODUCTION STRING</u>	
HOLE SIZE <u>7 7/8" T.D.</u>	DEPTH <u>5275'</u>
CASING SIZE <u>5 1/2"</u>	DEPTH
TUBING SIZE	DEPTH
DRILL PIPE	DEPTH
TOOL <u>PORT COLLAR</u>	DEPTH <u>3257'</u>
PRES. MAX	MINIMUM
MEAS. LINE	SHOE JOINT <u>42'</u>
CEMENT LEFT IN CSG. <u>42'</u>	
PERFS.	
DISPLACEMENT <u>125 BBLs</u>	
EQUIPMENT	
PUMP TRUCK # <u>422</u>	CEMENTER <u>TERRY</u>
	HELPER <u>WAYNE</u>
BULK TRUCK # <u>377</u>	DRIVER <u>ALLEN</u>
BULK TRUCK #	DRIVER

CEMENT	
AMOUNT ORDERED <u>175 SKS ASC 10% SALT</u>	
<u>5* GELSONITE 2.8 GEL 180F18</u>	
<u>500 GAL WFR-2</u>	
COMMON	@
POZMIX	@
GEL <u>3.5 SK</u>	@ <u>16.65</u> <u>49.95</u>
CHLORIDE	@
ASC <u>175 SKS</u>	@ <u>14.20</u> <u>2485.00</u>
	@
<u>SALT 95 SKS CWT</u>	@ <u>19.20</u> <u>172.80</u>
	@
<u>GELSONITE 875 #</u>	@ <u>5.70</u> <u>612.50</u>
	@
<u>FL-160 82 #</u>	@ <u>10.92</u> <u>873.30</u>
<u>WFR-2 500 GAL</u>	@ <u>1.00</u> <u>500.00</u>
	@
HANDLING <u>217 SKS</u>	@ <u>1.92</u> <u>412.30</u>
MILEAGE <u>94 PER SKI M/C</u>	@ <u>11.71</u> <u>80.00</u>
	@
TOTAL	<u>6277.65</u>

REMARKS:

MIX 500 GAL WFR-2 175 SKS
ASC 10% SALT 5* GELSONITE 180F18
FL-160 2% GEL. WASH TRUCK
+ LENS DISPLACE 125 BBL WATER.

PLUG LANDED AT 1800 PSI.
PISTON HELD

THANK YOU

CHARGE TO: PRESCO-WESTERN

STREET _____

CITY _____ STATE _____ ZIP _____

07019-KS
15055014
FDC

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SERVICE

DEPTH OF JOB <u>5296'</u>	
PUMP TRUCK CHARGE	<u>1840.00</u>
EXTRA FOOTAGE	@
MILEAGE <u>60 MI</u>	@ <u>6.00</u> <u>360.00</u>
MANIFOLD	@
<u>HEAD RENTAL</u>	@ <u>100.00</u>
	@
TOTAL	<u>2300.00</u>

5 1/2" PLUG & FLOAT EQUIPMENT

<u>1- Guide shoe</u>		<u>160.00</u>
<u>1- APU INSERT</u>	@	<u>250.00</u>
<u>7- CENTRALIZERS</u>	@ <u>50.00</u>	<u>350.00</u>
<u>1- BASKET</u>	@	<u>150.00</u>
<u>1- PORT COLLAR</u>	@	<u>1750.00</u>
<u>1- RUBBER PLUG</u>	@	<u>65.00</u>
	@	
TOTAL		<u>2725.00</u>

TAX _____

TOTAL CHARGE _____

DISCOUNT _____ IF PAID IN 30 DAYS

RECEIVED
KANSAS CORPORATION COMMISSION
OCT 25 2007

SIGNATURE _____

PRINTED NAME _____
CONSERVATION DIVISION
WICHITA, KS

ALLIED CEMENTING CO., INC. 25284

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:
OAKLEY

DATE 3-2-07	SEC. 26	TWP. 26S	RANGE 32W	CALLED OUT 3-2-07 4:30 PM	ON LOCATION 3-3-07 1:45 PM	JOB START 3-3-07 3:00 PM	JOB FINISH
LEASE ONESTING		WELL# 5-0	LOCATION GARDEN CITY 153-5E-4N-W		COUNTY FINNEY	STATE KS	
OLD OR <input checked="" type="radio"/> NEW (Circle one)							

CONTRACTOR CHEYENNE DRILL RIG #16	OWNER SAME
TYPE OF JOB SURFACE	
HOLE SIZE 12 3/4" T.D.	1717'
CASING SIZE 8 5/8"	DEPTH 1709'
TUBING SIZE	DEPTH
DRILL PIPE	DEPTH
TOOL	DEPTH
PRES. MAX	MINIMUM
MEAS. LINE	SHOE JOINT 40'
CEMENT LEFT IN CSG. 40'	
PERFS.	
DISPLACEMENT 106 1/4 BBLs	

EQUIPMENT			
PUMP TRUCK # 422	CEMENTER TERRY		
	HELPER WAYNE		
BULK TRUCK # 373	DRIVER LOUISE		
BULK TRUCK # 399	DRIVER REX		

CEMENT	AMOUNT ORDERED		
COMMON	150 SKS	@ 12.20	1830.00
POZMIX		@	
GEL		@	
CHLORIDE	24 SKS	@ 46.68	1118.70
ASC		@	
LITE	575 SKS	@ 11.30	6499.50
		@	
		@	
		@	
		@	
		@	
		@	
HANDLING	785 SKS	@ 1.90	1491.50
MILEAGE	90 PER SKI	MEILE	4239.00
			TOTAL 15464.40

REMARKS:
MIX 575 SKS LITE 3%CC 1/4" FLO
SEAL. 150 SKS COM 3%CC, DISPLACE
106 1/4 BBLs WATER. 70 Bbls to pits
CEMENT DID CIRC.
PLUG LANDED AT 1000' MEAS.
FLOAT HELD
THANK YOU

CHARGE TO: **PRESCO - WESTERN**

STREET _____

CITY _____ STATE _____ ZIP _____

De... 5-020-26-33
0701915
K505E014

To Allied Cementing Co., Inc.
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SERVICE			
DEPTH OF JOB	1709'		
PUMP TRUCK CHARGE			1610.00
EXTRA FOOTAGE	@		
MILEAGE	60 ME	@ 6.00	360.00
MANIFOLD	@		
HEAD RENTAL	@		100.00
	@		
			TOTAL 2070.00

8 5/8" PLUG & FLOAT EQUIPMENT			
1- GUARD SHOE			235.00
1- AFU INSERT	@		325.00
4- CENTRALIZERS	@ 55.00		220.00
1- BASKET	@		180.00
1- RUBBER PLUG	@		100.00
	@		
			TOTAL 1060.00

TAX _____

TOTAL CHARGE _____

DISCOUNT _____ IF PAID IN 30 DAYS

RECEIVED
KANSAS CORPORATION

SIGNATURE

OCT 29 2007
CONSERVATION DIVISION
WICHITA, KS

PRINTED NAME _____