

6050040

15-109-20332-00-00

R

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-109-20,332-00-00  
NW SW NE Sec. 18, T 11 S, R 33 (W/E)  
\_\_\_\_\_ feet from N/S section line  
\_\_\_\_\_ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5706

Lease Name Steele Well # 57-18

Operator: Fisrt Energy Corp.  
Name & Address: 16701 Greenpoint Park Dr.  
Suite 200  
Houston, Tx. 77060

County Logan  
Well Total Depth 4830 feet 156.98  
Conductor Pipe: Size 0 feet  
Surface Casing: Size 8 5/8 feet 302

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A XX

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Murfin Drilling Company License Number 6033 Rig tag 613

Address 250 N. Water Suite 300, Wichita, Ks. 67202

Company to plug at: Hour: \_\_\_\_\_ Day: 30 Month: July Year: 1984

VERBAL PLUGGING ORDERS GIVEN TO Bill Rider

(company name) Murfin Drilling Company (phone) \_\_\_\_\_

were: Order 195 sks 50/50 pozmix 6% gel 3% cal. cl., 1 sk flo-cel and 8 5/8" plug.  
Spot with drill pipe with no less than 36 vis. mud between all plugs. with good  
circulation and no fluid loss.

Signed \_\_\_\_\_ (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None XX

Operations Completed: Hour: 11:45 PM Day: 29th Month: July Year: 1984

ACTUAL PLUGGING REPORT

- 1st plug @ 2640 w/25 sks
- 2nd plug @ 1680 w/110 sks 1 sk flo-cel
- 3rd plug @ 320 w/40 sks
- 4th plug @ 40 w/8 5/8" plug 1/2 sk hulls 10 sks
- 10 sks in Rat Hole and 10 sks in Mouse Hole
- Cemented by Sun Cementing Company

Remarks: \_\_\_\_\_

RECEIVED  
STATE CORPORATION COMMISSION  
8-6-1984  
AUG 06 1984  
CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated  
and that I (did / did not) observe this plugging.

Signed Gilbert P. Liska (TECHNICIAN)

INVOICED

DATE 8-13-84

INV. NO. 2975

AUG 22 1984 SEP 12 1984

FORM CP-2/3  
Rev. 9-82  
8-3-84