

4-041776 15-109-20628-00-00

6-8

API Number: 15-109-20,628-00-00

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

C SE NW /4 SEC. 20, 11 S, 33 W
3300 feet from S section line
3300 feet from E section line

Operator license# 30407

Lease: Flipse Well # 1

Operator: Black Petroleum Company

County: Logan

Address: Box 12922
Wichita, Kansas 67277

Well total depth 4680 152.10 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 271 feet

Aband. oil well, Gas well, Input well, SWD, D & A X

Plugging contractor: L.D. Drilling, Inc. License# 6039

Address:

Company to plug at: Hour: A.M. Day: 8 Month: June Year 1996

Plugging proposal received from: Greg Davidson

Company: L.D. Drilling, Inc. Phone:

Were: Order 190 sxs 60/40 pozmix with 6% gel - 1/4# floseal per sack.
Spot plug through drill pipe with heavy mud between all plugs.

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All [], Part [], None [X]

Completed: Hour: 12:00 P.M., Day: 8, Month: June, Year: 1996

Actual plugging report:

- 1st. plug at 2625' w/25 sxs.
- 2nd. plug at 1650' w/100 sxs.
- 3rd. plug at 325' w/40 sxs.
- 4th. plug at 40' w/10 sxs.
- 15 sxs in rathole.

RECEIVED
KANSAS CORPORATION COMMISSION
7-16-1996
JUL 16 1996

CONSERVATION DIVISION
WICHITA, KS

Remarks: Allied Cementing.
Condition of casing(in hole): GOOD BAD Anhy. plug: YES X NO
Bottom plug(in place): YES, CALC, NO Dakota plug: YES X, NO
Plugged through TUBING, CASING. Elevation: 3148 GL

I did [] / did not [X] observe the plugging.

Dennis L. Hamel
(agent)

Form CP-2/3

INVOICE

DATE 7-16-96
INV. NO. 46016

10