

4-060284

12-21

230
R

15-109-20525-00-00

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-109-20,525-00-00

SW SE NE /4 SEC. 20 , 11 S , 33 W
2310 feet from S section line
990 feet from E section line

Operator license# 5123

Lease Vogler "A" well # 1

Operator: Pickrell Drilling Co., Inc.

County Logan

154.44

Address: 110 N. Market
Suite 205
Wichita, Kansas 67202

Well total depth 4752 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 276 feet

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: Pickrell Drilling Co., Inc. License# 5123

Address: Wichita, Kansas 67202

Company to plug at: Hour: 4:30A.M. Day: 21 Month: December Year: 91

Plugging proposal received from: Doyle Folkerts

Company: Pickrell Drilling Company, Inc. Phone: 316-262-8427

Were: Order 190 sxs. 60/40 posmix - 6% gel. with 1/4# flocele per sx.
Space all plugs with heavy drilling mud through drill pipe.

RECEIVED
STATE CORPORATION COMMISSION
1-6-1992
JAN 08 1992
CONSERVATION DIVISION
WICHITA, KANSAS

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 4:30A.M., Day: 21, Month: December, Year: 91

Actual plugging report:

1st. plug at 2640' with 25 sxs. - Anhydrite 2623' - 2650'.

2nd. plug at 1650' with 100 sxs. - Dakota 1341' - 1641'.

3rd. plug at 330' with 40 sxs. - Surface pipe to 276'.

4th. plug at 40' with 10 sxs.

Rathole with 15 sxs.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD - BAD - Anhy. plug: YES X NO

Bottom plug(in place): YES , CALC , NO Dakota plug: YES X, NO

Plugged through TUBING , CASING . Elevation: 3141 GL

INVOICED

I did [] / did not [X] observe the plugging.

Herb Deines

DATE 1-10-92

INV. NO. 34308

12-21

Herb S.

(agent)

Form CP-2/3