

7-18

4-110024

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
100 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number 15-109-20,601-0001
110' N. of SE SE SE / 4 SEC. 11 S, 33 W
440 feet from S section line
330 feet from E section line

Operator license# 31120
Operator: Pelican Hill Oil & Gas, Inc.
Address: 1401 N. ElCamino Real - #203
San Clemente, CA 92672

(Formerly Scheetz #1)
Lease: Washdown ONWO Well # 1
County: Logan 77.87
Well total depth 2396 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8" Inch @ 250 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Abercrombie RTD, Inc. License# 30684

Address: 150 N. Main - Suite #801 - Wichita, Kansas 67202

Company to plug at: Hour: P.M. Day: 18 Month: July Year: 1997

Plugging proposal received from: Tony Martin

Company: Abercrombie RTD, Inc. Phone: 316-262-1841

Were: According to KCC Rules & Regulations.

8-11-97

Plugging Proposal Received by: Roger Moses

Plugging operations attended by agent? All[], Part[], None[]

Completed: Hour: 4:30 P.M., Day: 18, Month: July, Year: 1997

Actual plugging report: Old well work over. 8 5/8" to 253'. Drilled to a depth of 2396' and lost the hole. Pulled to 1640' and pumped 100 sxs cement. Pulled pipe to 310' and pumped 40 sxs cement. Pulled to 40' and pumped 10 sxs. Pumped 15 sxs in rathole - 10 sxs in mousehole. Total of 175 sxs 60/40 pozmix and 6% gel with 1/4# floseal per sack.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD BAD Anhy.plug: YES NO

Bottom plug(in place): YES CALC NO Dakota plug: YES NO

Plugged through TUBING , CASING Elevation: 3130 GL

I did[] / did not[] observe the plugging.

Roger Moses
(agent)

Form CP-2/3

INVOICED

DATE 8-5-97

INV. NO. 48719

8-5 (Did not receive Original)