

2-18

4-061049

15-109-20640-00-00

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-109-20,640-00-00

C SW /4 SEC. 22, 11 S, 33 W
1320 feet from S section line
3960 feet from E section line

Operator license# 5003

Lease Soucie "A" Well # 1-22

Operator: McCoy Petroleum Corporation

County: Logan 154.96

Address: 3017 N. Cypress Street
Wichita, Kansas 67226-4003

Well total depth 4768 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 262 feet

Aband. oil well, Gas well, Input well, SWD, D & A X

Plugging contractor: Sweetman Drilling Company License# 5658

Address: Wichita, Kansas 67202

Company to plug at: Hour: 10:30 P.M. Day: 17 Month: February Year: 1997

Plugging proposal received from: Brad

Company: Sweetman Drilling Company Phone:

Were: Order 200 sxs 60/40 posmix - 6% gel with 1/4# floseal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All [], Part [], None [X]

Completed: Hour: 12:30 A.M., Day: 18, Month: February, Year: 1997

Actual plugging report:

1st. Plug at 2660' w/25 sxs. Anhydrite 2642' - 2667'.

2nd. Plug at 1650' w/100 sxs. Dakota 1350' - 1650'.

3rd. Plug at 315' w/40 sxs. Surface pipe at 262'.

4th. Plug at 40' w/10 sxs.

15 sxs in rathole.

10 sxs in mousehole.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD X BAD Anhy.plug: YES X NO

Bottom plug(in place): YES, CALC, NO X Dakota plug: YES X, NO

Plugged through TUBING, CASING. Elevation: 3150 GL

I did [] / did not [X] observe the plugging.

DATE 3-5-97

INV. NO. 47698

2-18

RECEIVED
KANSAS CORP CONM
1997 MAR -3 P 1:59
3-5-1997

[Signature]
PK (agent)