

15-109-20518-00-00

10-15

256

R

6-060264

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-109-20,518-00-00

SE SE SW /4 SEC. 22, 11 S, 33 W
330 feet from S section line
2310 feet from E section line

Operator license# 4629 Lease Saucie "B" well # 1-22

Operator: Brito Oil Company, Inc. County Logan 153.40

Address: 200 E. First Well total depth 4720 feet
Suite 208 Conductor Pipe: 0 inch @ 0 feet
Wichita, Kansas 67202 Surface pipe 8 5/8 Inch @ 251 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Blue Goose Drilling License# 5104

Address: Great Bend, Kansas 67530

Company to plug at: Hour: 2:00A.M Day: 15 Month: October Year: 91

Plugging proposal received from: Martin Miller

Company: Blue Goose Drilling Phone: _____

Were: Order 190 sxs. 60/40 posmix - 6% gel. - 1/4# flocele per sx.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All , Part , None

Completed: Hour: 2:00A.M. Day: 15 Month: October Year: 91

Actual plugging report: _____

1st. plug at 2650' with 25 sxs. Anhydrite 2634' - 2664'.

2nd. plug at 1645' with 100 sxs. Dakota 1344' - 1644'.

3rd. plug at 305' with 40 sxs. Surface pipe to 251'.

4th. plug at 40' with 10 sxs.

Rathole with 15 sxs.

RECEIVED

10-30-1991

OCT 30 1991

CONSERVATION DIVISION
Wichita, Kansas

Remarks: By: Allied Cementing.

I did not observe the plugging.

INVOICED

DATE 11-8-91

INV. NO. 33663

J. S.

(agent)

Form CP-2/3