

15-109-20060-00-00

10-23-87

6 030981

API NUMBER 15- 2-11-76

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

NW/NW, SEC. 23, T 11 S, R 33 (W/E)  
4620 feet from S section line  
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5992

Lease Name Bertrand Well # 2

Operator: Patton Oil Co.  
Name & Address: 672 West Fourth  
Hoisington, Kansas 67544

County Logan 152.26  
Well Total Depth 4685 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 258

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Chase, Kansas

Company to plug at: Hour: AM Day: 23 Month: Oct. Year: 19 87

Plugging proposal received from Ronnie

(company name) Kelso (phone) \_\_\_\_\_

were: 8 5/8" set at 258' cwc 5 1/2" set at 4683' w/125 sks. Perf. 4317' - 4283'  
PBTD 4350'. Order sand and Common Cement. Pull pipe. Order 200 sks ATL 5 sks Hulls.

Allied Cement+Co. Newman Water truck. 65/35 Pozmix 10% Gel 2% Dicol Cement Blend.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 10:00 AM Day: 23 Month: Oct. Year: 19 87

ACTUAL PLUGGING REPORT Sand bottom to 4230' w/5 sks Common Cement on sand w/bailer.

2 shots at 2700' and 1900'. Recovered 1900' of 5 1/2" casing. Squeezed 8 5/8" w/5 sks Hulls  
in w/200 sks ATL Cement Blend. Max Psi 800#. Close in Psi 300#. Plug complete.

RECEIVED  
STATE CORPORATION COMMISSION

NOV 18 1987  
11-18-1987

Remarks: (If additional description is necessary, use BACK of this report.)

INVOICED

observe this plugging.

Signed Carl Goodrow (TECHNICIAN)

DATE 12-3-87

INV. NO. 19060

Carl Goodrow