

6-100447

1-14
15-109-20527-00-00

66
R

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-109-20,527-00-00

SE SE NW /4 SEC. 23, 11 S, 33 W
2310 feet from S section line
2310 feet from E section line

Operator license# 5123

Lease Cassidy "A" well # 1

Operator: Pickrell Drilling Co., Inc.

County Logan

Address: 110 North Market
Suite 205
Wichita, Kansas 67202

Well total depth 4725 feet
Conductor Pipe: inch @ feet
Surface pipe 8 5/8 Inch @ 320 feet

153.56

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: Pickrell Drilling Company License# 5123

Address: Wichita, Kansas

Company to plug at: Hour: ?? Day: Month: Year:

Plugging proposal received from: Doyle Folkers

Company: Pickrell Drilling phone:

Were: **Spot plugs through drill pipe w/ heavy mud between all plugs.**

1st plug @ 2635 feet with 25 sacks Rat hole: 15 sacks

2nd plug @ 1630 feet " 100 " Mousehole: sacks

3rd plug @ 370 feet " 40 "

4th plug @ 40 feet " wiper plug & 10 sacks

5th plug @ feet

Plugging Proposal Received by: David K. Wann

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 2:15 am, Day: 14, Month: January, Year: 1992

Actual plugging report: Hole reported plugged as above.

Order 190 sx 60/40 pozmix w/ 6% gel and 2 sx celloflake or flowcel.

RECEIVED
STATE CORPORATION COMMISSION
2-10-1992
FEB 10 1992
CONSERVATION DIVISION
WICHITA, KANSAS

Remarks: Elevation: 3126 GL, Anhydrite depth: 2632 - 2650 feet
Anhy. plug: YES Dakota plug: YES Bottom hole plug in place: YES
Plugged through drill pipe: YES
Did NOT penetrate Arbuckle, cemented by Allied

INVOICED

I did[] / did not[X] observe the plugging.

David K. Wann
David K. Wann P.I.R.T. II
(agent)

DATE 2-18-92
INV. NO. 34588

Lib. S.