

10-3 15-109-20517-00-00

22
R

6-070961

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-109-20,517-00-00

SW SE NW /4 SEC. 24, 11 S, 33 W
2310 feet from S section line
1650 feet from E section line

Operator license# 5046

Lease Kulhman well # 1

Operator: Raymond Oil Co. Inc.

County Logan

Address: P.O. Box 48788
Wichita, Kansas 67202

Well total depth 4462 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 303 feet

145.01

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Murfin Drilling Company License# 30606

Address: Wichita, Kansas 67202

Company to plug at: Hour: P.M. Day: 3 Month: October Year: 91

Plugging proposal received from: Keith Vanpelt

Company: Murfin Drilling Company Phone: 316-267-4214

Were: B 5/8" 303' S.P. cvc. w/225 sx. 60/40 pozmix - 3% c.c. - 2% gel.
by Halco. Miss well. No circulated problems. Mud 48 vis. - 9.2 Wt. -
9.5 W.L. Elv. 3107' - Anhy. 2603'. Proposal 190 sx. 60/40 pozmix
6% gel. - 3% c.c. Circulate hole. Spot with drill stem. Heavy mud
between all plugs. 25 sx. @ 2610' - 100 sx. w/1 sx. F.C. @ 1600' -
40 sx. @ 350' - 10 sx. @ 40'. 15 sx. Rathole (cir.)

Plugging Proposal Received by: Marion J. Schmidt
Plugging operations attended by agent? All , Part , None

Completed: Hour: 10:45P.M., Day: 3, Month: October, Year: 91

Actual plugging report: Raymond Oil Company ordered 190 sx. 60/40
pozmix - 6% gel. - 3% c.c. Circulated hole - mud between all plugs
42 to 45 vis. Spot with drill stem.

1st. plug 25 sx. @ 2610'.
2nd. plug 100 sx. w/1sx. F.C. @ 1600'.
3rd. plug 40 sx. @ 350'.
4th. plug 10 sx. @ 40'.
15 sx. in Rathole (cir.)

Remarks: Cemented by: Halliburton

I did did not observe the plugging.

Marion Schmidt

INVOICED
DATE 11-14-91
INV. NO. 33720

Gilm. S.

(agent)
Form CP-2/3