

11-28
4-062553 15-109-20522-00-00

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-109-20,522-00-00

S2 NE NE 1/4 SEC. 25, 11 S, 33 W
4290 feet from S section line
660 feet from E section line

Operator license# 5422 Lease Ehrlich well # 1

Operator: Abercrombie Drilling, Inc. County Logan

Address: 150 N. Main Suite 801 Wichita, Kansas 67202
Well total depth 4680 feet 152.10
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 272 feet w/190 sx.

Aband. oil well __, Gas well __, Input well __, SWD __, D & A X

Plugging contractor: Abercrombie R.T.D. Inc. License# 30684

Address: 150 N. Main, Suite 801, Wichita, Kansas 67202

Company to plug at: Hour: 11:30A.M Day: 25 Month: November Year: 91

Plugging proposal received from: Tony Martin

Company: Abercrombie R.T.D., Inc. Phone: 316-262-1841

Were: Order 190 sks. 60/40 pozmix - 6% gel. - 3% cal. cl., -
1 sk. flo-cel and 8 5/8" plug. Spot with drill pipe with no less than
36 vis. mud between all plugs, with good circulation and no fluid loss.

Plugging Proposal Received by: Gilbert G. Scheck
Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 3:15A.M, Day: 28, Month: November, Year: 91

Actual plugging report:
1st plug @ 2600' w/25 sks.
2nd plug @ 1600' w/100 sks. - 1 sk. flocele.
3rd plug @ 300' w/40 sks.
4th plug @ 40' w/10 sks.

RECEIVED
STATE CORPORATION COMMISSION
12-12-1991
DEC 12 1991

15 sks. in Rathole.

Remarks: Cemented by: Allied.

CONSERVATION DIVISION
Wichita, Kansas

I did [] / did not [X] observe the plugging.

Gilbert G. Scheck

INVOICED
DATE DEC 12 1991
NO. 34191

(agent)
Form CP-2/3