

4-14 15-109-20208-00-01

To: 6 031243
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- OWWO
NE NE NW 25 11 33
, SEC. , T S, R W/E

4950 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3567

Lease Name James Well # 1

Operator: Totten Resources Inc.
Name & Address 2506 Greenleaf Court

County Logan 153.14

Well Total Depth 4712 feet

Wichita, Ks. 67226

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 370

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated Allied

Plugging Contractor Russell, Ks. License Number

Company to plug at: Hour: AM Day: 14 Month: April Year: 19 89

Plugging proposal received from Dean Ives

(company name) Totten (phone)

were: 8 5/8" set at 370' cwc 4 1/2" set at 4375' w/150 sks. PBD 4344'

Perfs 4286' - 90' . Shots at 2613' Anhy at 1850' Base Dakota. Order

50 sks cement for bottom; Pull pipe. Order 225 sks 65/35 Poz 10% Gel 2% Dixel

500# Hulls. Allied.

STATE CORPORATION COMMISSION
STATE COMMISSION
5-10-1989
MAY 10 1989

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None x

Operations Completed: Hour: 10:30AM Day: 14 Month: April Year: 19 89

ACTUAL PLUGGING REPORT Sand bottom to 4235' w/4 sks common cement on sand w/bailer.

Three shots recovered 1408' of casing. Squeezed 8 5/8" of 225 sks cement

blend to max psi 300#. Close in psi 150#. Plug complete.

Remarks: (If additional description is necessary, use BACK of this form.)

I (XXXX) did not observe this plugging.

INVOICED

Signed Carl Goodrow (TECHNICIAN)
Carl Goodrow

DATE 5-12-89

INV. NO. 24805

JUN 1 2 1989