

15-109-20184-00-00

API NUMBER 15- 109 20184-00-00

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

NE Sec. 25, T 11 S, R 33 WE  
990 feet from N/S section line  
1650 feet from WE section line  
Lease Name Phalick Well # 1

TECHNICIAN'S PLUGGING REPORT

Operator License # 5267

County LOGAN

Operator: K & E PETROLEUM INC.  
Name &  
Address HARDAGE CENTER, SUITE 300  
WICHITA, KANSAS.

Well Total Depth 4780 feet \$155.35

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 7/8 feet 348

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor KELSO CASING PULLING License Number 547-551  
6050

Address CHASE, KANSAS

Company to plug at: Hour: AM Day: 27 Month: 4 Year: 19 83

VERBAL PLUGGING ORDERS GIVEN TO DON COOL

(company name) KELSO CASING PULLING (phone) \_\_\_\_\_

were: BOTTOM PLUG - PUSH 60SX COM. CEM. AND

4 1/2" WIPER PLUG TO TOP OF CEMENT AT 3500'

SHOOT OFF AND PULL PIPE PERFS 4625-30 & 4283-86

THIS WELL WAS GASING

WIPER PLUG - COM. CEM.

Signed Carl Goodrow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 9:30 AM Day: 27 Month: 4 Year: 19 83

ACTUAL PLUGGING REPORT BOTTOM PLUG - PUSHED WIPER PLUG BEHIND

60 SX. COM. CEM. WENT ON VACUUM - PUSHED 2<sup>ND</sup> WIPER PLUG

BEHIND 50 SX. OF COM. CEM. STOPPED AT 3400'.

10 SHOTS WERE AT 3448-2881-2640-2439-2197-2003-1797-1675-1555-1434

PULLED 1434' OF 4 1/2" TOP PLUGGED BY SQUEEZING DOWN 8 5/8" WITH

2 HULLS - 17 SX GEL - 100 SX CEM. 23 SX GEL. - 8 5/8" PLUG - 70 SX CEM.

Remarks: CEM > 50/50 P026% GEL. 3% CC

SHUT IN 300 PSI

I hereby certify that the above plugging instructions were given as herein stated.  
and that I (did / did not) observe this plugging.

INVOICED

RECEIVED STATE CORPORATION COMMISSION

Signed Carl Goodrow  
(TECHNICIAN)

DATE 5-6-83

5-2-1983  
MAY 02 1983

FORM CP-2/3  
Rev. 9-82

INV. NO. 4202-W - CONSERVATION DIVISION  
Wichita, Kansas