

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-00009-00-00
Spot: NWSW Sec/Twnshp/Rge: 28-9S-17W
1980 feet from S Section Line, 4620 feet from E Section Line
Lease Name: REMPE A Well #: 1
County: ROOKS Total Vertical Depth: 3620 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S MARKET
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	155	0	w/130 sxs cmt
PROD	4.5	3619	0	w/unknown sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/21/2009 12:30 PM
Plug Co. License No.: 33930 Plug Co. Name: SUPER OILWELL SERVICE
Proposal Rcvd. from: DAVE FUNK Company: KANSAS CORPORATION COMMIS Phone: (785) 625-0550

Proposed Plugging Method: Ordered out 300 sxs 60/40 pozmix - 4% gel - 500# hulls.

20090056001-control #

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/21/2009 3:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Unable to get tubing below 1850' (casing parted).
Loggers unable to get perforating gun below 1150'. Perforated 950' and 150'.
Ran tubing to 1820'. Quality Oil Well Cementing pumped 50 sxs 60/40 pozmix - 4% gel neat.
Pulled tubing to 937'. Pumped 165 sxs cement with 450# hulls - cwc out 4 1/2" casing.
Shut in 4 1/2" backside - pumped 25 sxs cement - circulated cement out of 8 5/8".
PTOH. Topped off 4 1/2" casing with 25 sxs cement - casing full.

Perfs:

Top	Bot	Thru	Comments
3533	3534		
3507	3513		
3494	3496		
3464	3468		
3444	3452		

RECEIVED
MAY 27 2009
KCC WICHITA

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #3138.

Plugged through: TBG

District: 04

Signed

Richard Williams

(TECHNICIAN)

CM

DAVIS BROTHERS

#1 REMPE 'A'

28-9-17W
C NW SW

Contr. WOODMAN & IANNITTI

ROOKS

County

2119RB Comm. 4-24-62 Comp. 5-31-62

135 BOPD LANS

MARM 3444-3534

SPL Tops	Depth	Datum
'A' ZN	3279-3307	-1160
'B'	3315-32	-1196
'D'	3335-50	-1206
E F & G	3360-3405	-1241
H	3415-30	-1296
I	3440-50	-1321
J	3458	-1339
K	3483-98	-1364
L	3500-14	-1381
MARM	3528-42	-1409
LOG TOPS		
TOP	3023	-904
WEB	3237	-1118

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

Casing
8" 155/130 SX
4" 3619
DST 3243-3350/2 HRS, 210' M...
M, BHP 870-760# 139', FF 130-
210#
DST 3347-3409/2 HRS, 210' M...
SW, BHP 1095-980# 130' 210'
230-320#
DST 3398-3550/2 HR, 120' M...
O, 240' HO & GEN, 130' M...
100' M, BHP 1115
1025# 130', FF 130'
475#
(COVER)

DAVIS BROS

#1 REMPE 'A'

28-9-17W

ADDITIONAL LOG TOPS:

TOR	3260	-1141	PERF (MARM) 3533-34, 'L' ZN
LANS	3281	-1162	3507-13: 'K' 3494-96: ACID
B/KC	3514	-1395	500: FU 800' FIH/12 HRS: SWB
CONG	3539	-1420	DOWN: SWB 5 BF/1ST HR, 95% O
SIMP DOL	3596	-1477	1 1/2 BF/2ND, 97% O: REACID 3000
ARB (SPL)	3616	-1497	SWB LD: SWB 18 BOPH/1ST & 2ND
			HRS: 13 1/2 BOPH/3. & 4TH HR: 11.
TD	3620	-1501	76 BO/6TH HR: PB 3475: PERF 'I'
			3444-52: 'J' 3464-68: SWB 8 BO
			ACID 3000: FU 3075 F: SWB DN:
			SWB LD: SWB 23 1/2 BO/1ST: 20 BO/
			2ND: 18 1/2 BO/3RD: 15 BO/4TH: CO
			PLUG 3475: SWB FROM ALL PERFS
			25 BOPH/1ST HR