

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-20255-00-00
Spot: SWSW Sec/Twnshp/Rge: 28-9S-17W
660 feet from S Section Line, 4620 feet from E Section Line
Lease Name: REMPE A Well #: 2
County: ROOKS Total Vertical Depth: 3560 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S MARKET
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	170	0	w/130 sxs cmt
PROD	4.5	3558	0	w/275 sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/20/2009 8:00 AM
Plug Co. License No.: 33930 Plug Co. Name: SUPER OILWELL SERVICE
Proposal Rcvd. from: DAVE FUNK Company: KANSAS CORPORATION COMMIS Phone: (785) 625-0550

Proposed Plugging Method: Ordered out 275 sxs 60/40 pozmix - 4% gel - 600# hulls.
Bridges at 900' to 1100' - unable to get below 1315'.

20090056002-control #

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/20/2009 10:20 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 1283'. Quality Oil Well Cementing pumped 50 sxs 60/40 pozmix neat.
Pulled to 876'. Quality pumped 105 sxs cement with 300# hulls - circulated cement.
PTOH. Squeezed 40 sxs cement.
Max. P.S.I. 400#. S.I.P. 300#.
Hooked up to backside - pumped 40 sxs cement.
Max. P.S.I. 400#. S.I.P. 400#.

Perfs:

Top	Bot	Thru	Comments
3501	3505		
3487	3490		
3455	3461		
3446	3448		
3436	3443		
3418	3423		
3411	3414		

RECEIVED
MAY 27 2009
KCC WICHITA

Remarks: QUALITY OIL WELL CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

Richard Williams

(TECHNICIAN)

CM

DAVIS BROTHERS
TULSA, OKLA.

#2 REMPE 'A'

28-9-17W
C SW SW

Contr. WOODMAN & IANNITTI

Cty. ROOKS

Geol.

Pool NETTIE NW CONF

E. 2117 KB Cm. 9/25/69 Cp. 11/6/69 IP PMP 20 BOPD + 100

API 15-163-20,255

BWPD/LKC 3411-
3501

SMP Tops	Depth	Datum
ANH	1410	+ 707
TOP	3014	- 897
HEEB	3230	-1113
TOR	3254	-1137
LKC	3274	-1157
BKC	3506	-1389
CONG	3536	-1419
RTD	3560	-1443

Csg. 8-5/8" 170/130 SX
4 1/2" 3558/275 SX

PF (LANS) 16/3501-05, 12/3487-
90, 12/3477-80, A 4000, SEP
PF 24/3455-61, 8/3446-48, 28/
3436-43, A 1250, SWB TST, RE-
ACID ALL PFS 3500 GALS, 700#
MOTHBALLS, PF 20/3418-23, PF
12/3411-14, A 3000, POP

NO DSTS
NO LOG