

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-20271-00-00
Spot: NESE Sec/Twnshp/Rge: 29-9S-17W
1980 feet from S Section Line, 660 feet from E Section Line
Lease Name: REMPE B Well #: 2
County: ROOKS Total Vertical Depth: 3570 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S MARKET
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF		0		
SURF	8.625	161	0	w/130 sxs cmt
PROD	4.5	3569	0	w/200 sxs cmt

Well Type: EOR UIC Docket No: E15389.1 Date/Time to Plug: 05/21/2009 3:30 PM
Plug Co. License No.: 33930 Plug Co. Name: SUPER OILWELL SERVICE
Proposal Rcvd. from: DAVE FUNK Company: KANSAS CORPORATION COMMIS Phone: (785) 625-0550

Proposed Plugging Method: Ordered out 300 sxs 60/40 pozmix - 4% gel - 8 sxs gel spacer - 600# hulls.
1500' with Black Magic to surface.
Injection perms: 3389' - 3520'.

20090056003-control #

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/21/2009 6:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perforated two shots at 1750' - 1460' - 950' - 150'.
Ran tubing to 2795' - hit hard bottom - junk in the hole.
Pulled to 2785' - Quality Oil Well Cementing pumped 100 sxs 60/40 pozmix - 4% gel with 400# hulls.
Pulled to 1314' - pumped 100 sxs cement with 150# hulls - cwc.
Shut in 4 1/2" and pumped 40 sxs cement - circulated out of 8 5/8".
PTOH. Topped off 4 1/2" casing with 20 sxs cement.

Perfs:

Top	Bot	Thru	Comments
3513	3515		
3500	3503		
3491	3494		
3469	3474		
3454	3458		

RECEIVED
MAY 27 2009
KCC WICHITA

Remarks: SCOUT CARD INDICATES LEASE NAME REMPE B-1. QUALITY OIL WELL CEMENTING-TICKET #3139.

Plugged through: TBG

District: 04

Signed

Richard Williams

(TECHNICIAN)

CM

154

DAVIS BROTHERS
TULSA, OKLA.

#1 REMPE 'B'

29-9-17W
C NE SE

Contr. WOODMAN & JANNITI

Cty. ROOKS

Geol.

Pool NETTIE NW

E. 2123 RB Cm. 11/13/69 Cp. 12/18/69 IP SWD/LANS 3425-3515

API 15-163-20,271

SMP Tops	Depth	Datum
ANH	1450	+ 673
B ANH	1460	+ 663
TOP	3031	- 908
HEEB	3247	-1124
TOP	3267	-1144
LANS	3289	-1166
RTD	3523	-1400

Csg. 8-5/8" 161/130 SX
4 1/2" 3568/200 SX

PF 3513-15, 3491-94, 3500-3503
3469-74, 3454-58, SSO, A 5500,
FU 1800' FL, SWB 54 BF, 5% OIL
BP 3442, SWB 12 BF, 15% OIL/1ST
HR, FL 2200' FS, TOP 100' OIL,
SWB 18.54 BF, 5% OIL,
SWDWINJ RATE SATIS.

NO DSTS
NO LOG
NO CORES

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS