

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-20940-00-00  
Spot: SWSESW Sec/Twnshp/Rge: 34-13S-15W  
330 feet from S Section Line, 3630 feet from E Section Line  
Lease Name: MARY A COADY Well #: 1  
County: RUSSELL Total Vertical Depth: 3360 feet

Operator License No.: 101  
Op Name: KCC FEE FUND PLUG  
Address: 130 S MARKET  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	647	0	w/400 sxs cmt
PROD	5.5	3359	0	w/150 sxs cmt

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/15/2009 2:30 PM  
Plug Co. License No.: 33930 Plug Co. Name: SUPER OILWELL SERVICE  
Proposal Rcvd. from: TIM BILERY Company: KANSAS CORPORATION COMMIS Phone: (785) 625-0550

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 11 sxs gel spacer - 500# hulls.

20090057003-control #

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 05/15/2009 5:15 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 2998' - pumped 11 sxs gel spacer - followed with 50 sxs cement and 200# hulls.  
Pulled tubing to 1650' - pumped 145 sxs cement with 200# hulls - cement circulated to pit.  
Pulled tubing out of well - hooked up the casing and pumped 70 sxs cement - cement circulated out of braden head.  
Topped casing with two sxs of cement.

Perfs:

Remarks: QUALITY CEMENTING SERVICE-TICKET #3118.

Plugged through: TBG

RECEIVED  
JUN 01 2009  
KCC WICHITA

District: 04

Signed

Ray AD. KD

(TECHNICIAN)

CM

121

34-13-15W  
SW SE SW

DRISCOLL LEASE OPERATIONS

#1 MARY A. COADY

726 MAIN  
RUSSELL, KS.

CONTR . EMPHASIS OIL OPERATIONS CTY RUSSELL

GEOL J. R. GREEN FIELD GORHAM

E 1896 KB CM 9/11/76 CARD ISSUED 5/5/77 IP P 50 BOPD, N/W LKC 3079-83

+	+	+
+	+	+
+	+	+

API 15-167-20,940

LOG	TOPS	DEPTH	DATUM
SC		926	+ 970
TARK		2524	- 628
LANS		3053	-1157
BKC		3298	-1402
GOR SD		3311	-1415
RTD		3360	-1464

8-5/8" 647/400sx, 5 1/2" 3359/150sx  
 MICT - PF 3312-13, FU 2000' FL (10% o)  
 SET BP @ 3200, PF (LKC) 3079-83, AC  
 1000, REC LD, SWB 6 BOPD, N/W, POP

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS