

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-22464-00-00
Spot: SESESW Sec/Twnshp/Rge: 34-13S-15W
330 feet from S Section Line, 2970 feet from E Section Line
Lease Name: MARY A COADY Well #: 2
County: RUSSELL Total Vertical Depth: 3369 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S MARKET
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	572	0	w/290 sxs cmt
PROD	5.5	3369	0	w/235 sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/18/2009 11:30 AM
Plug Co. License No.: 33930 Plug Co. Name: SUPER OILWELL SERVICE
Proposal Rcvd. from: DAVE FUNK Company: KANSAS CORPORATION COMMIS Phone: (785) 625-0550

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 11 sxs gel spacer - 200# hulls.
Perf: 1650' - 950' - 150'.

20090057002-control #

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/18/2009 3:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 2998' - pumped 11 sxs gel spacer - 50 sxs cement with 200# hulls.
Pulled tubing to 1650' - pumped 150 sxs cement - cement circulated the 5 1/2" casing.
Closed backside - pumped 85 sxs cement - cement circulated out the braden head.
Pulled tubing out - topped off casing with 15 sxs cement.

Perfs:

RECEIVED
MAY 27 2009
KCC WICHITA

Remarks: QUALITY CEMENTING SERVICE-TICKET #3134.

Plugged through: TBG

District: 04

Signed

Ray A. Dinkel

(TECHNICIAN)

CM

DRISCOLL LEASE OPERATIONS, INC.
726 MAIN #2 MARY A. COADY


34-13-15W
SE-SE SW

RUSSELL, KS 67665

CONTR REVLIN DRILLING CTY RUSSELL

GEOLOG ROY KRUEGER FIELD GORHAM

ELV 1903 K B SPD 10/7/84 CARD ISSUED 1/31/85 IP P 15 BO & 50 BWPD
1898 GL LKC 3067-3110 OA



LOG	Top	Depth/Datum
ANH		937+ 966
TARK SD		2474- 571
TARK LM		2533- 630
HOW		2732- 829
TOP		2970-1067
HEEB		3012-1109
TOR		3032-1129
LKC		3064-1161
BKC		3310-1407
GOR SD		3320-1417
RTD		3374-1471

API 15-167-22,464

8-5/8 " 572 / 290SX; 5-1/2 " 3369 / 235SX
LM, MED XLN, W/ TR FO, NO ODOR FROM 2533-40
LM, FINE XLN, CHTY, ISOLATED SFO & SPTD STN, GD ODOR
FROM 3066-70
LM, CHLKY TO POORLY OOLICASTIC, ISOLATED SFO & FAIR
SPTD STN, FAIR ODOR FROM 3090-94 & 3107-10
ROUNDED, WELL SORTED, WELL CONSOLIDATED, MED
GRAINED, SAND CLUSTERS, W/ STR ODOR, GD STN & SATURA-
TION FROM 3321-24
OIL SHOWS DECRD, ODOR REMAINED STRONG & CLUSTERS BE-
CAME MORE COARSE GRAINED FROM 3324-74
NO DSTS
MICT - CO, PF (LKC) 3067-70, 3090-94 & 3106-10, W/ 4 SPF,
AC 3000G (15%), SWB DWN, SO, POP, P 15 BO & 50 BWPD (GR
35") 11/15/84

COPYRIGHT 1984
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS