

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-02381-00-02  
Spot: SESWNW Sec/Twnshp/Rge: 32-10S-22W  
2970 feet from S Section Line, 4290 feet from E Section Line  
Lease Name: GRIFFITH 'A' Well #: 1  
County: GRAHAM Total Vertical Depth: 3940 feet

Operator License No.: 101  
Op Name: KCC FEE FUND PLUG  
Address: 130 S MARKET  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	207	0	150 SX
T1	2	3867		
DVT		1748		
PROD	4.5	3900	0	150/350 SX

Well Type: SWD UIC Docket No: D24942.0 Date/Time to Plug: 05/18/2009 12:00 PM  
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.  
Proposal Rcvd. from: OZZIE VANAUSDALE Company: KANSAS CORPORATION COMMIS Phone: (785) 625-0550

Proposed Plugging Method: Ordered 170 sxs 60/40 pozmix - 4% gel - 150# hulls.  
PBTD 1650'. Pulled 47 joints of seal-tite out of hole - collar parted above packer - left packer in the hole.

20090031003 - control #

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 05/18/2009 12:30 AM KCC Agent: PAT STAAB

Actual Plugging Report:

Quality Cementing rigged to 4 1/2" casing - pumped 120 sxs cement with 150# hulls mixed in.  
Max. P.S.I. 500#. S.I.P. 350#.  
Rigged to 8 5/8" - instant pressure.  
Max. P.S.I. 300#. S.I.P. 300#.

Perfs:

Top	Bot	Thru	Comments
1480	1530		Cedar Hills


KANSAS CORPORATION COMMISSION  
JUN 03 2009  
RECEIVED

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #3155.

Plugged through: CSG

District: 04

Signed



(TECHNICIAN)

CM

AMERICAN PETROLEUM  
COMPANY, INC.

400 N. WOODLAWN, #111  
WICHITA, KS. 67208

#1 'A' GRIFFITH 'OWWO' 32-10-22W  
SE SW NW

CONTR R & C DRILLING, INC. CTY GRAHAM

GEOLOGICAL FIELD LACERTE

ELV 2288 KB SPD 10/29/84 CARD ISSUED 9/5/85 IP P 24 BO & 35 BWPD  
LKC 3629-3763.5

API 15-065-01,009

SMP	Tops	Depth/Datum
HEEB		3529-1241
LANS		3566-1278
BKC		3970-1682
SIMP SH		3971-1683
SIMP SD		3980-1692
ARB		ABSENT
RTD		4000-1712

OLD INFO: OPERATOR WAS COLORADO OIL & GAS CORP., #1 'A' GRIFFITH, SPD 6/7/57, SET 8 5/8 " 207, COMP AS D&A/SIMP 6/18/57 (CARD ISSUED 6/28/57), CONTR: GARVEY DRILLING  
DST (1)-3560-95 (LANS) / OP 60", REC 38" M, SIP 1105#, FP NA  
DST (2) 3594-3635 (LKC) / OP 60", REC 32" M, W/SL SCUM OIL, SIP 700#, FP NA

NEW INFO: FR 10/18/84, RE-ENTERED 10/29/84, WSH DWN TO 3900, SET 4 1/2 " 3900 /-125SX--MICT--CO: PF (LKC) 1 / 3763.5, 1 / 3728, 1 / 3744, AC 750G (15% MA), SWB DWN, SO, PF (LKC) 3746-50, W / 2 SPF, AC 2000G (15% DEMUL), SWB DWN, SO, PF (LKC) 1 / 3629, AC 250G (15% MA), SWB DWN, SO, RE-PF (LKC) 3629-33, W / 2 SPF, AC 1500G (15% DEMUL), SWB DWN, SO, SET 2" TBG AT 3867, POP, P 24 BO & 35 BWPD, 11/26/84

*now for 5-10-87*

COPYRIGHT 1985  
INDEPENDENT OIL & GAS SERVICE, INC.  
WICHITA, KANSAS