

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-22338-00-00  
Spot: SWSENW Sec/Twnshp/Rge: 32-10S-22W  
2970 feet from S Section Line, 3630 feet from E Section Line  
Lease Name: GRIFFITH Well #: 2  
County: GRAHAM Total Vertical Depth: 3850 feet

Operator License No.: 101  
Op Name: KCC FEE FUND PLUG  
Address: 130 S MARKET  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	214	0	w/140 sxs cmt
PROD	4.5	3849	0	w/450 sxs cmt

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/18/2009 9:00 AM  
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.  
Proposal Rcvd. from: OZZIE VANAUSDALE Company: KANSAS CORPORATION COMMIS Phone: (785) 625-0550

Proposed Plugging Method: Ordered 305 sxs 60/40 pozmix - 4% gel - 350# hulls.  
Alliance washed and drilled down on well to 420'. Ran into junk in the hole.  
May have drilled out of casing. Could not get down any further.

20090031001-control #

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 05/18/2009 11:35 AM KCC Agent: PAT STAAB

Actual Plugging Report:

Quality Cementing rigged to 8 5/8" - pumped 5 sxs cement.  
Max. P.S.I. 300#. S.I.P. 300#.  
Rigged to 4 1/2" casing - pumped 125 sxs neat cement - followed with 175 sxs with 350# hulls mixed in.  
Well went on small vacuum.  
Left set 45 minutes.  
Topped off with 5 sxs cement. Hole standing full.  
Had 600# P.I.P. on well.

Perfs:

Top	Bot	Thru	Comments
3601	3604		LKC

KANSAS CORPORATION COMMISSION  
JUN 03 2009  
RECEIVED

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #3154.

Plugged through: CSG

District: 04

Signed \_\_\_\_\_

(TECHNICIAN)

CM

MAY 28 2009

361

AMERICAN PETROLEUM  
COMPANY, INC.  
400 N. WOODLAWN, #111  
WICHITA, KS. 67208

#2 GRIFFITH

32-10-22W  
SW SE NW

CONTR R & C DRILLING

CTV GRAHAM

OPER RON NELSON

FIELD WC(LACERT REV)

+	+	+
+	+	+
+	+	+

REV 2285 KB SPD 11/20/86 CARD ISSUED 1/1/87 TO P 30 BO & 50 RWPD  
2280 GL DRLG COMP 11/28/86 LKC 3601-3604

LOG	Tops	Depth/Datum	API 15-065-22,338
ANH	1782+	503	8 5/8" 214 / 140 SX, 4 1/2" 3849 / 450 SX.
HIEER	3524	1239	NO CORES
TOB	3546	1261	DST (1) 3591-3615 (LANS) / 30-30-30-30. REC 200' SLI MCO,
LANS	3561	1276	240' HMCO, 60' OCMW, 120' SW, SIP 665-665#, FP 39-108 /
RLC	3781	1496	137-206#, HP 1906-1892#
IID	3850	1565	MICR - CO, PF (LKC) 1 / 3602.5. AC 350 GAL (15% MCA), SWB
			DWN, SO, PF (LKC) 3601-3604, W / 2 SPF, AC 350 GAL (15%
			MCA), SWB DWN, SO, SET 2" TRG AT 3727, POP, P 30 BO & 50
			RWPD (GR 35%), 12/10/86

AMERICAN PETROLEUM COMPANY  
WICHITA, KANSAS