

4 060089

5-18

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING,  
WICHITA, KANSAS 67202

API NUMBER 15-163-21,201-0000

NE SE NE, SEC. 34, T 10 S, R 16 W/EX

3630 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7076

Lease Name Nelson A Well # 1

Operator: Black Diamond Oil, Inc.

County Rooks 118.37

Name & Address 3004 Broadway Ave.

Well Total Depth 3642 feet

Hays, KS 67601

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 250

Abandoned Oil Well XXXXXXXXXX Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Co. Tools License Number \_\_\_\_\_

Address Hays, KS

Company to plug at: Hour: 9:30AM Day: 18 Month: May Year: 1990

Plugging proposal received from Ken Vehige

(company name) Black Diamond Oil, Inc. (phone) 913-625-5891

were: Perforate at 725' (Base of Dakota) and 1165' (Anhydrite)

Order 65/35 Pos 8% gel and hulls.

Fluid level very low.

Tubing pulled prior to plugging. Hole open and in good condition.

Plugging Proposal Received by Herb Deines  
(TECHNICIAN)

Plugging Operations attended by Agent?: All XXXXXXXXXX Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12:45PM Day: 18 Month: May Year: 1990

ACTUAL PLUGGING REPORT 8 5/8" at 250', 5 1/2" at 3575' No casing pulled.

Pumped 425 sxs. of 65/35 Pos 8% gel and 700# of hulls. Max press. 800# SIP 700#.

Pumped 50 sxs. of 65/35 pos 8% gel and 100# hulls down annulus. Max Press. 800# SIP 500#

Cement top next day at surface.

Remarks: RECEIVED STATE CORPORATION COMMISSION  
and Allied Cementing  
(If additional description is necessary, use BACK of this form.)

INVOICED 1990

observe this plugging.

DATE 6-5-90 CONSERVATION DIVISION

INV. NO. 28295

*Herb S.*

Signed Herb Deines  
(TECHNICIAN)  
Herb Deines