

4-17

368 R

163-23,166 - 0000

6 070913

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-
SE NW SE 16 T 10 S, R 16 W7E
1370 feet from S section line
1750 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5537
Operator: Brown Enterprises Kenny
Name & Address: Drawer 340
Plainville, Ks. 67663
Kenny Brown

Lease Name K. Brown Well # 6
County Rooks Rooks 104.58
Well Total Depth 3218 feet
Conductor Pipe: Size 0 feet
Surface Casing: Size 8 5/8 feet 2078

Abandoned Oil Well Gas Well Input Well SWD Well D&A xx

Other well as hereinafter indicated

Plugging Contractor Western Ks. Drilling License Number 4083
Address Hays, Ks.

Company to plug at: Hour: Am Day: 17 Month: april Year: 19 91

Plugging proposal received from Dwight French Frank Taggart

(company name) Western Ks. Drilling (phone)

were: 8 5/8 207 ft. s.p. cwc w/145 sks 60/40 poz 2% gel 3% ca cl. By Halliburton

Arb at 3590 - KC well - Elv. 2066 Anhy 1289. Mud and condition 43 vis.

RECEIVED
STATE CORPORATION COMMISSION
4-26-91
APR 26 1991

9.8 weight. 10 water loss. No circulation problems. Proposal 215 sks
60/40 poz 6% gel 3% calcl. 1 sk f.c. spot with drill stem displace with

mud 25 sks at 3500 ft. 25 sks at 1260 - 100 sks w/1 sk f.c. at 770 ft.

CONSERVATION DIVISION
Wichita, Kansas
40 sks at 250 10 sks at 40 ft. 15 sks in rathole. Circulate.
Plugging Proposal Received by Marion J. Schmidt
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: Day: 17 Month: 4 Year: 19 91

ACTUAL PLUGGING REPORT Brown Ent. ordered 190 sks 60/40 poz 6% gel and 1 sk f.c.

Circulated hole. Spotted cement through drill stem. Mud between cement
plugs. Did not penetrate arb. 1st plug at 1260 w/25 sks cement.

2nd plug at 770 w/100 sks cement w/1 sk f.c. 3rd plug at 250 w/40 sks cemen

4th plug at 10 sks at 40 ft. 15 sks in rathole. Circ.

By Halliburton Cement.

Remarks: (if additional description is necessary, use BACK of this form.)

INVOICED

(operator did not observe this plugging.)

DATE 5-7-91
INV. NO. 31766

Handwritten initials

Signed Marion J. Schmidt
(TECHNICIAN)