

6 110034

API NUMBER 15-163 22,797-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SW SW 1/4 SEC. 16, T. 10 S, R. 16 W/E
2880 2970 feet from S section line
RT FCC 4950 feet from E section line

Geologist
TECHNICIAN'S PLUGGING REPORT

Operator License # 5068

Lease Name Post Well # 1

Operator Name & Address Black Petroleum Co.

County Rooks 110.37

527 Union Center Bldg

Well Total Depth 3396 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8" feet 289 ✓

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Red Tiger Drilling, Inc License Number 5302

Address _____

Company to plug at: Hour: _____ Day: _____ Month: _____ Year: 19 _____

Plugging proposal received from Walt Oden

(company name) Red Tiger (phone) _____

were: Order 220 SX 60/40 Pozmix 6% gel 3 SX Flo-seal

Heavy mud between all plugs spotted through drill pipe. Cement added to top as plugs may slip because of lost circulation zones. Anhydrite 12.75-13.11

lost circulation at 2303', 2587', 3316' - was regained

No Ar buckle Plugging Proposal Received by _____

2085-1600 = 985 + 0.50 = 735 Anhydrite (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 9:00 PM Day: 12/11 Month: 11 Year: 19 85

ACTUAL PLUGGING REPORT 1st plug 2200' 30 SX + 1 SX Flo-seal

Through Mr. Schmidt: 1290' 30 SX + 1 SX Flo-seal

Will tag top plug, add 750' 100 SX + 1 SX Flo-seal

any cement as needed 330' 40 SX

if plugs slip. 40' 10 SX on solid bridge

Applied Rathok 10 SX

Remarks: _____ (If additional description is necessary, use BACK of this form.)

INVOICED
DATE DEC 10 1985
WV. NO. 11354

RECEIVED
12-9-85
DEC 9 1985

Signed Michael K Larson 19 12-6-85
(TECHNICIAN)