

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-01840-00-00
Spot: NENENE Sec/Twnshp/Rge: 22-10S-16W
4950 feet from S Section Line, 330 feet from E Section Line
Lease/Unit Name: CONGER B Well Number: 1
County: ROOKS Total Vertical Depth: 3686 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S. MARKET
WICHITA, KS 67202

Production Casing Size: 2.875 feet: 3658
Surface Casing Size: 8.625 feet: 240 w/175 sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/08/2003 10:30 AM
Plug Co. License No.: 3152 Plug Co. Name: POE SERVICING INC
Proposal Rcvd. from: ED POE Company: POE SERVICING INC Phone: (785) 475-3422

Proposed Plugging Method: Ordered out 100 sxs 60/40 pozmix - 10% gel.

Plugging Proposal Received By: JAY PFEIFER WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 07/08/2003 5:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Perforated casing at 820' and 1250'.
Tied onto 2 7/8" - mixed and pumped 100 sxs cement.
Max. P.S.I. 700#. S.I.P. 500#.
Annulus full of cement.

RECEIVED
7-11-03
JUL 11 2003
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed _____

(TECHNICIAN)

JUL 09 2003

CITIES SERVICE PETR #1 CONGER 'B' 22-10-16W
NE NE NE

Contr. LEBEN DR LG ROOKS County

E. 2093 DF Comm. 2-27-62 Comp. 4-27-62 IPCAL PMP 108 B0 & 73
BWPD/CONG 3601-23

Log Tops	Depth	Datum
ANH	1235	+808
TOP	2988	-895
HEEB	3223	-1130
TOR	3245	-1152
LANS	3269	-1176
B/KC	3540	-1447
CONG	3606	-1513
ARB	3671	-1578
TD	3686	-1593

Casing
8" 240/175 SX
2" 3658
DST 3013-59/90", 10' OCM, 60' SL G & GCM,
60' M, O/S, BHP 950-730#/30", FP 35-70"
DST 3305-45/90", WK BLO/4", 28' M, BHP
720-105#/30", FP 20-20"; DST 3350-95/90",
387' MDY SW, BHP 1145-1090#/30", FP 30-185"
DST 3445-75/1 HR, 20' M, FBHP 390#/30": DST
3600-30/1 HR, 15' SL OCM, 120' OCM, 180'
H OCM, 300' SL MCG, 360' SL MG & GCD, 60'
SL COMDY W, 60' SW, FBHP 870#/30": DST 3630
-45/1 HR, 30' M, FBHP 205#/30"
OO 3642: PB TD: 16/3619-23: 40/3606-16: 20/
NATOMA POOL

						3601-06: SWD 44 GO & 56 G MDY
						w/11 HRS: 2" TSG 3683: SWD
						26 BO & WTR/11 HRS: RMP 32
						BO & 49 SW/17 HRS

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

Dak 488 - 788
Ark 1735 - 1765
Salt 1610 - 1747