

15-051-05019-0001

9-9

4-041934  
RECEIVED  
KANSAS CORP COM  
11-5-97  
1997 NOV -5 D  
SW NE 1/4

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15-051-97,607

SW NE 1/4 SEC. 02, 11 S, 16 W  
990 feet from N section line  
990 feet from E section line

Operator license# 5447 Lease: Gish C (Krueger 704) Well # 4

Operator: OXY USA, Inc. County: Ellis 114, 34

Address: Drawer D Well total depth 3518 feet  
Plainville, Kansas 67663 Conductor Pipe: 0 inch @ 0 feet  
Surface Pipe: 8 5/8 Inch 248 Feet  
W/175 sxs cmt.

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 8:00 A.M. Day: 9 Month: September Year 1997

Plugging proposal received from: J.D. Hininger

Company: OXY USA, Inc. Phone: 913-434-7681

Were: 5 1/2" casing set at 3518' w/175 sxs cement.  
Perfs at 2936' - 3415'. Anhy. At 1625' w/400 sxs cement. W.L.M. at 3107'.  
Ordered 225 sxs 60/40 pozmix - 10% gel with 1/4# F.C. - 500# hulls - 18 sxs gel.

Plugging Proposal Received by: Dennis Hamel

Plugging operations attended by agent? All [ X ], Part [ ], None [ ]

Completed: Hour: 10:30 A.M., Day: 9, Month: September, Year: 1997

Actual plugging report: R.U. Cementers to 5 1/2" casing. Squeezed 40 sxs cement with 200# hulls, followed with 18 sxs gel, followed with 190 sxs cement with 200# hulls.  
Max. P.S.I. 800#. S.I.P. 600#.  
R.U. Cementers to 8 5/8" S.P. Squeezed 25 sxs cement with 100# hulls. Max. P.S.I. 200#. S.I.P. 200#.

Remarks:  
Condition of casing (in hole): GOOD X BAD  
Bottom plug (in place): YES X, CALC, NO  
Plugged through TUBING, CASING. Elevation: G.L.

I did [ X ] / did not [ ] observe the plugging.

Dennis L. Hamel  
(agent)  
Form CP-2/3

INVOICED

DATE NOV 06 1997

INV. NO. 49449

9-9, JAN 09 1998