

12-10-96

15-051-19233-0003

4-041884

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15- - 1949

NW SW NW /4 SEC. 02, 11 S, 16 W
3630 feet from S section line
4950 feet from E section line

Operator license# 5447

Lease: Krueger Well # 503S

Operator: OXY USA, Inc.

County: Ellis 113.16

Address: 110 S. Main - #800
Wichita, Kansas 67202

Well total depth 3482 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 309 feet
w/ 175 sxs.cmt.

Aband. oil well, Gas well, Input well, SWD, D & A SUPPLY X

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 12:00P.M Day: 22 Month: December Year 1996

Plugging proposal received from: Gary Wagner

Company: OXY USA, Inc. Phone:

Were: 5 1/2" casing set at 3481' w/200 sxs.
Ordered 150 sxs 60/40 pozmix - 10% gel - with 1/4# F.C. plus 200# hulls.
Perfs. at 613' - 810'. Squeeze at 752' w/200 sxs. Packer at 3295' - CIBP at 3240'. Set
cement Rtr. at 1601'. Plug back with 200 sxs. Casing filled to 780' and drilled out to 988'
and milled to 1030' and plug back to 820'.

Plugging Proposal Received by: Dennis Hamel
Plugging operations attended by agent? All[], Part[], None[X]

3-12-97
RECEIVED
KANSAS CORP COM

Completed: Hour: 12:00 P.M., Day: 10, Month: December, Year: 1996

Actual plugging report: 11-22-96 - Cleaned out well to 621'. R.U. Allied Cementing -
pumped 105 sxs 60/40 pozmix with 10% gel plus 100# hulls. Circulated cement to surface.
P.O.O.H. with tubing and squeezed 20 sxs cement. Max. P.S.I. 300#. 8 5/8" S.P. - Pressured
up to 500#.
12-10-96 - Ran W.H.M. to 216'. Filled to surface with 25 sxs cement.

Remarks:
Condition of casing(in hole): GOOD BAD X Anhy.plug: YES X NO
Bottom plug(in place): YES X, CALC, NO Dakota plug: YES X, NO
Plugged through TUBING X, CASING. Elevation:

I did[] / did not[X] observe the plugging.

DATE MAR 12 1997

INV. NO. 47742

Dennis L. Hamel
(agent)

12-10