

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-19027-00-00
Spot: NENWNW Sec/Twnshp/Rge: 2-11S-16W
517 feet from N Section Line, 738 feet from W Section Line
Lease/Unit Name: KRUEGER UNIT Well Number: 501 AS
County: ELLIS Total Vertical Depth: 919 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 8100 E. 22ND N. BLDG. 300
WICHITA, KS 67226

Conductor Pipe: Size feet: 35.00
Surface Casing: Size 8.625 feet: 304 175 SX
Production: Size 7 feet: 913 200 SX
Liner: Size feet:

Well Type: WSW UIC Docket No: Date/Time to Plug: 04/11/2002 8:00 AM
Plug Co. License No.: 32452 Plug Co. Name: SMOKY HILLS WELL SERVICE
Proposal Rcvd. from: JOEL STULL Company: VESS OIL CORPORATION Phone: (785) 885-4352

Proposed Plugging Method: Ordered 175 sxs 60/40 pozmix - 10% gel - 500# hulls.
T.O.F. at 260'.

Plugging Proposal Received By: DENNIS HAMEL WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 04/11/2002 1:00 PM KCC Agent: DENNIS HAMEL

Actual Plugging Report:

RIH with tubing to 613'. Hit solid bridge.
Pumped 100 sxs cement to circulate tubing and 7" casing at surface.
Shut in casing.
Fluid also circulated 7" annulus with cement.
Circulated to surface.
POOH with tubing and filled 7" casing with 25 sxs cement.

RECEIVED
4-30-02
APR 30 2002
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed Dennis J. Hamel
(TECHNICIAN)

APR 23 2002

INVOICED
DATE 5-01-02
INV. NO. 2002061721

WELL RECORD

Company Cities Service Oil Company Well No. 901 AB Farm Krueger Dale
Location 517' FWL 799' FWL Sec. 2 T. 11S R. 16W
Elevation 2081 GL County Rock State Kansas
Initial Prod. _____ Contractor Reel Bros. Inc.
Acid _____ Drlg. Comm. _____
T. D. 919' Drlg. Comp. _____

casing Record:

7" @ 913' w/200 Str.

Electric Log Data:

Nebraska 914' (+1567)

Formation Record:

Depth

<u>Rock & Clay</u>	<u>0 - 60</u>
<u>Chalk & Shale</u>	<u>60 - 795</u>
<u>Sand</u>	<u>795 - 890</u>
<u>Chalk</u>	<u>890 - 915</u>

RECEIVED
KANSAS CORPORATION COMMISSION

JAN 17 2002

CONSERVATION DIVISION