

4-042034

E-15,354-0004
20240-0001

API Number: 15-163-90695-0000
RTKCC

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

SE SW SW _____ /4 SEC. 02 , 10 S, 17 W
330 feet from S section line
4290 feet from E Section line

Operator license# 31008

Lease: Rolfe Well # 2

Operator: Paul Bowman Oil

County: Rooks 113.75

Address: 801 Codell Road
Plainville, Kansas 67663

Well total depth 3500 feet
Conductor Pipe: 0 inch @ 0 feet
Surface Pipe: 8 5/8 Inch 209 Feet
W/150 sxs.cmt.

Aband. oil well _____, Gas well _____, Input well X, SWD _____, D & A _____

Plugging contractor: Allied Cementing License# _____

Address: Russell, Kansas 67665

Company to plug at: Hour: 8:00 A.M. Day: 8 Month: February Year 2000

Plugging proposal received from: Paul Bowman

Company: Paul Bowman Oil Phone: _____

Were: Ordered 200 sxs 60/40 pozmix - 10% gel with 1/4# F.C. plus 400# hulls.
5 1/2" casing set at 3498' w/150 sxs cement. Perf. 3150' - 3466'.
Perf salt at 1900'. Anhy at 1300'. Casing squeeze at 800' w/100 sxs cement.

Plugging Proposal Received by: Dennis Hamel
Plugging operations attended by agent? All[], Part[X], None[]

Completed: Hour: 11:00 A.M. , Day 8, Month: February , Year: 2000

Actual plugging report: Ran in hole with tubing to 3050'. Spotted 30 sxs cement with 300# hulls, followed with 12 sxs gel. Pulled tubing to 1300'. Spotted 100 sxs cement to circulate at surface. POOH with tubing. Squeezed casing with 30 sxs cement.
Max. P.S.I. 800#. S.I.P. 400#.
8 5/8" S.P. - Squeezed 25 sxs cement with 100# hulls. Max. P.S.I. 300#. S.I.P. 100#.

Remarks: _____
Condition of casing(in hole): GOOD _____ BAD _____ Anhy.plug: YES _____ NO _____
Bottom plug(in place): YES _____, CALC _____, NO _____ Dakota plug: YES _____, NO _____
Plugged through TUBING _____ CASING _____ . Elevation: _____ G.L. _____

I did[X] / did not[] observe the plugging.

INVOICED
DATE 2/15/00
INV. NO. 06/252

Dennis Hamel
RECEIVED
STATE CORPORATION COMMISSION
Form CP-2/3
FEB 15 2000
2-15-00
CONSERVATION DIVISION
Wichita, Kansas

R