

10-22

191R

4-031608

"CORRECTED"

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-163-20,170-0000

NW SE NW /4 SEC. 02, 10 S, 17 W
3630 feet from S section line
3630 feet from E section line

Operator license# 6566 Lease Melville well # 1

Operator: Leben Oil Corporation County Rooks 114.85

Address: Box 21468 Well total depth 3534 feet
Tulsa, Oklahoma 74121-1468 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 211 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Kelso Casing Pulling License# 6050

Address: Chase, Kansas

Company to plug at: Hour: P.M. Day: 22 Month: October Year: 91

Plugging proposal received from: Vernon Duntz

Company: Kelso Casing Pulling Phone:

Were: 8 5/8" set @ 211' w/150 sx. cwc. 5 1/2" set @ 3532' w/200 sx.
P.B.T.D. 3534'. Perf. 3188' - 3457'. Order sand and common cemnt.
Pull pipe. Order 425 sx. 65/35 poz. 10% gel. 500# hulls. Allied
Cement Company. Keller Water Truck. Hole open across perf.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 1:00P.M. Day: 22 Month: October Year: 91

Actual plugging report: Sanded back to 3110' w/5 sx. common cement
on sand with bailer. One shot recovered 1900' of 5 1/2" casing.
Laid down to 1200' anhy. Pump bottom plug through 5 1/2" casing
w/225 sx. cement blend. Laid down 5 1/2" casing. Squeezed 8 5/8" with
total 425 sx. cement blend w/500# hulls mixed in to max. P.S.I. 600#.
Close in P.S.I. 500#.

RECEIVED
STATE CORPORATION COMMISSION

Remarks: Anhy. 1200'.

12-2-91
DEC 02 1991

CONSERVATION DIVISION
WICHITA, KANSAS

I did[X] / did not[] observe the plugging. Carl Goodrow

INVOICED

DATE 12-9-91

Feb 9.

(agent)
Form CP-2/3

INV. NO. 34054

10-22 JAN 28 1992