

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

APT NUMBER 15  
NE NE, Sec. 13, T 11 S, R 16 W/E

R

330 feet from N/S section line  
990 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5447

Lease Name Kruger Unit Well # 401 W  
County Ellis

Operator: Cities Service Co.  
Name & Address 209 E. William, 800 Sutton Place,  
Wichita, Mo. 67202

Well Total Depth 3560 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8" feet 313 302

PT  
KCC

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well  SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Halliburton Services License Number 5287  
Address 1600 E. 8th, Hays, Mo. 671601

Company to plug at: Hour: 2:00 PM Day: 12 Month: 10 Year: 1982

VERBAL PLUGGING ORDERS GIVEN TO Dan Huffman  
(company name) Cities Service Co. (phone) 913-434-2350

were: Order 215 sacks 50 normix - 4% Gel. - 3% ball, 4 sacks hulla, 15 sacks Gel + 5 1/2" plug. Pumped in 8 5/8" 35 sacks cement. Pumped in 5 1/2" 25 sacks cement, 4 sacks hulla, 12 sacks Gel, 70 sacks cement, 3 sacks Gel, 1 sack hulla, released plug & followed w/ 85 sacks cement.

Signed Walter E. Schel  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 3:45 PM Day: 12 Month: 10 Year: 1982

ACTUAL PLUGGING REPORT 8 5/8" 313' SP. CUC. W/ 175 sacks common. 5 1/2" set at 3523' W/ 200 sacks common. Top perf at 3205'. Well had been squeezed at 1110'. Plugged back to 3205'. Ordered 215 sacks 50 normix - 4% Gel. - 3% ball, 4 sacks hulla, 15 sacks Gel, & 5 1/2" plug. Pumped in 8 5/8" 35 sacks cement. Pumped in 5 1/2" 25 sacks cement, 4 sacks hulla, 12 sacks Gel, 70 sacks cement, 3 sacks Gel, 1 sack hulla, released plug & followed w/ 85 sacks cement.

Remarks: Maximum pressure 200 pounds.  
Checked cement top & pumped 4 sacks of hulla & 60 sacks cement in 5 1/2" casing plugged from 622' to surface.

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 19 1982  
10-19-82  
CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above plugging instructions were observed and that I (did) did not) observe this plugging.

Signed Walter E. Schel  
(TECHNICIAN)

INVOICED

DATE 10-25-82  
INV. NO. 1424-A

FORM CP-2/3  
Rev. 9-82

D