

4-042032

15-163-20183-0000

API Number: 15-163-20183-0000 N/A

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

SE NE SE /4 SEC. 03 , 10 S, 17 W
1650 feet from S section line
330 feet from E Section line

Operator license# 31008

2/3

Lease: Anspaugh Well # 4

Operator: Paul Bowman Oil

County: Rooks 112.39

Address: 801 Codell Road
Plainville, Kansas 67663

Well total depth 3458 feet
Conductor Pipe: 0 inch @ 0 feet
Surface Pipe: 8 5/8 Inch 219 Feet
W/135 sxs.cmt.

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 12:00 P.M. Day: 3 Month: February Year 2000

Plugging proposal received from: Paul Bowman

Company: Paul Bowman Oil Phone: -

Were: Ordered 185 sxs 60/40 pozmix - 10% gel with 1/4# F.C. plus 300# hulls - 12 sxs gel
5 1/2" casing set at 3456' w/150 sxs cement. Perf. 3126' - 3393'.
Perf salt at 1900'. Anhy at 1300'. T.O.F. at 1200'.
Prior squeeze casing at 700' with cement N/A.
Tubing fish at 3200'.

Plugging Proposal Received by: Dennis Hamel

Plugging operations attended by agent? All[], Part[X], None[]

Completed: Hour: 3:30 P.M. , Day 3, Month: February , Year: 2000

Actual plugging report: R.I.H. with tubing to 3000'. Spotted 12 sxs gel followed with 40 sxs cement with 300# hulls to plug bottom. Pulled tubing to 1500'. Spotted 120 sxs cement - did not circulate. Pulled tubing.
02-04-2000 - Ran W.L.M. - T.O.C. at 1700'. T.O.F. at 1000'. Ran in hole with tubing to 1675'. Spotted 125 sxs cement to circulated at surface. P.O.O.H. with tubing - filled casing with 10 sxs cement. Job completed.

Remarks:

Condition of casing(in hole): GOOD X BAD Anhy.plug: YES X NO
Bottom plug(in place): YES X, CALC, NO Dakota plug: YES X, NO
Plugged through TUBING X CASING Elevation: G.L.

I did[X] / did not[] observe the plugging.

INVOICED

DATE 2/15/00

INV. NO. 061252

Dennis L. Hamel (agent)

RECEIVED Form CP-2/3
STATE CORPORATION COMMISSION

2-15-00
FEB 15 2000

CONSERVATION DIVISION
Wichita, Kansas

(R)