

15-163-00273-0001

3-4 4-031892

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- - 1950

NW NW SW /4 SEC. 03, 10 S, 17 W
2310 feet from S section line
4950 feet from E section line

Operator license# 5229 Lease Nettie Unit well #11-01

Operator: Phillips Petroleum Company County Rooks

Address: Rt. 3 - Box 20A Well total depth 3617 feet
Great Bend, Kansas 67530 Conductor Pipe: s inch @ 0 feet
Surface pipe 8 5/8 Inch @ 184 feet

117.55

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Kelso Casing Pulling License# 6050

Address: Chase, Kansas 67524

Company to plug at: Hour: P.M. Day: 4 Month: March Year: 94

Plugging proposal received from: Richard - Dennis Hamel

Company: Kelso Casing Pulling - Kansas Corporation Commission Phone:

Were: Order 260 sxs. 60/40 pozmix - 10% gel - 400# hulls.
Halliburton. - Order sand and common cement.

Plugging Proposal Received by: Carl Goodrow
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 5:30P.M., Day: 4, Month: March, Year: 94

Actual plugging report: Sand back to 3170' with 5 sxs. common cement on
sand with bailer. Critical shot areas are at Base Salt 1800' - Anhy. at
1300' - Base Dakota 800'. Shot and recovered 630' of 5 1/2". Shot at
2200' - 1800' - 1300'. Pipe tight. Mixed and pumped 85 sxs. cement
blend with 200# hulls displaced from 850' to 2200' with 500# P.S.I. Shot
at 800'. Pipe tight. Shot free at 630'. Mixed and pumped 110 sxs. cement
with 200# hulls to 800' with annulus. Circulate with heavy drill mud.
Laid down to 184' circulated cement to surface with 55 sxs. Slurry.
Laid down 5 1/2" casing. Topped off 8 5/8" with 10 sxs. Slurry. Plug complete.

Remarks:
Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO
Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X, NO
Plugged through TUBING , CASING X. Elevation: GL

I did X did not observe the plugging. RECEIVED Goodrow
STATE CORPORATION COMMISSION

DATE MAR 29 1994
INV. NO. 40173

MAR 16 1994 (agent)
3-16-94
CONSERVATION DIVISION
Wichita, Kansas
Form CP-2/3