

6 041278

8-31-90  
API NUMBER 15-163-03561-0000

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

SE E NE, SEC. 4, T 10 S, R 17 W4E33

2970 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5229

Lease Name Nettie Well # 6-3

Operator: Phillips PetCo..

County Rooks 114.33

Name & Address route #3 Bx 20 A

Well Total Depth 3518 feet

Great Bend, Ks. 67530

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 237 cwc

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing License Number

Address Box 147 Chase, Ks67524

Company to plug at: Hour: 12:00PM Day: 31 Month: August Year: 19 90

Plugging proposal received from Millard Kelso

(company name) Kelso Casing (phone)

were: 5 1/2 casing set at 3515 w/150 sks cement.

Plug bottom w/sand to 3164 plus 5 sks cement:

Shot pipe at 1400 - 800 and 175.

Ordered 300 sks 65/35 poz 10% gel w/1/2 lb f.c. plus 5 sks hulls.

Plugging Proposal Received by Dennis L. Hamel

(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 12:00PM Day: 31 Month: August Year: 19 90

ACTUAL PLUGGING REPORT Hooked up to 5 1/2 casing: pumped in 150 sks cement

w/2 sks hulls; Max 800 lbs SI 400 lbs. Hooked up to 8 5/8 s. p. : pumped in

100 sks cement w/2 sks hulls Max 300 SI 200 lbs.

RECEIVED  
STATE CORPORATION COMMISSION

4-4-91  
APR 04 1991

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: If additional description is necessary, use BACK of this form.)

INVOICED

(did / 318-888) observe this plugging.

DATE APR 05 1991

INV. NO. 31327

J.L.S.

Signed Dennis L. Hamel  
(TECHNICIAN)  
Dennis L. Hamel