

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-20315-00-00  
Spot: SESENW Sec/Twnshp/Rge: 4-10S-17W  
2160 feet from S Section Line, 2970 feet from E Section Line  
Lease/Unit Name: SCHRANDT Well Number: 4  
County: ROOKS Total Vertical Depth: 3515 feet

Operator License No.: 5252  
Op Name: NIXON, R P OPERATIONS, INC  
Address: 207 W 12TH  
HAYS, KS 67601

Production Casing Size: 5.5 feet: 3508 175 SX CMT  
Surface Casing Size: 8.625 feet: 218 150 SX CMT

*114 24*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/30/2003 9:30 AM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: PAUL NIXON Company: NIXON, R P OPERATIONS, INC. Phone: (785) 628-3834

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 10% gel - 500# hulls.  
PBTD 3488'.  
Squeezed jobs as follows: 01-23-75 - 906' w/150 sxs. 12-19-76 - 2984' w/100 sxs.  
12-12-85 - 2989' w/200 sxs. 02-28-92 - 2707'-2753' w/100 sxs. 02-28-92 - 1867' w/250 sxs.  
03-05-92 - 2134'-2261' w/200 sxs. 03-10-92 - 3034' w/25 sxs. 03-11-92 -2150'-2170' w/25 sxs.

Plugging Proposal Received By: HERB DEINES WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 07/30/2003 10:30 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Allied pumped 250 sxs 60/40 pozmix - 10% gel with 500# hulls.  
Max. P.S.I. 600#. S.I.P. 200#.  
Hooked up to backside - instant 800# pressure.

RECEIVED  
8-1-03  
AUG 01 2003  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed

*Richard Williams*

(TECHNICIAN)

INVOICED

DATE 8-1-03

INV. NO. 2004060303

Form CP-2/3

JUL 30 2003

CLINTON OIL CO. #4 SCHRANDT 4-10-17W  
 WICHITA, KANSAS APP SE SE NW  
 CONTR RED TIGER DRLG. CTY ROOKS  
 GEOL TOM SATTIER FIELD NETTIE  
 E 207.7 KB CM 6/10/70<sup>CARD</sup> ISSUED 7/23/70 IP P 25 BOPD 7% WTR  
 ARB 3508-15  
 GR 35

API 15-163-20,315

LOG	TOPS	DEPTH	DATUM	
ANHY		1356	+ 721	DST(1) 3177-3248/90", 80'GIP, 25'M W/SP O OIL, BHP
B ANHY		1384	+ 693	464-455//30", FP 50-54//
TOP		2964	- 887	DST(2) 3246-3270/1 1/2", 625'GIP, 192'GOM, BHP 794-722#
HEEB		3180	-1103	/30", FP 27-54// & 63-109#
TOR		3204	-1127	DST(3) 3290-3340/90", 2250'GIP, 750'MW, BHP 891-874#
LANS		3222	-1145	FP 54-313// & 313-393#
BKC		3460	-1383	DST(4) 3372-3420/90", 20'SOCM, 20'VHOCM, BHP 406-
MRM		3478	-1401	330//30", FP 40-44// & 44-53//
ARB		3504	-1427	DST(5) 3490-3518/2", 700'GIP, 140'MO N/W, BHP 936-
LTD		3514	-1437	829//30", FP 34-38// & 45-80//
DDTD		3515	-1438	MICT, CO TD FU 320'/12HRG BAIL DRY, SWB 1060 PLUS
				TR WTR DD 3515 BAIL 2 BO NEXT 4HRS AC 250, SWB LD,
				SWB 5 BO PLUS TR W/1 1/2HRS SD/12 FU 500' BAIL DRY SWB
				1.87BO PLUS TR W/1HR, 1.50BO PLUS TR W/2ND HR, 1.20
				BO PLUS TR W/3RD HR SD/12 FU 1750'FL SWB DWN & REC
				11.25 BO PLUS TR WTR, POP

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS