

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-19005-00-00  
Spot: N2N2NW Sec/Twnshp/Rge: 4-10S-17W  
4950 feet from S Section Line, 3960 feet from E Section Line  
Lease/Unit Name: SCHRANDT Well Number: 2  
County: ROOKS Total Vertical Depth: 3519 feet

Operator License No.: 5252  
Operator Name: NIXON, R P OPERATIONS, INC  
Address: 207 W 12TH  
HAYS, KS 67601

Conductor Pipe: Size feet:  
Surface Casing: Size 8.625 feet: 176  
Production: Size 5.5 feet: 3517  
Liner: Size feet:

114.37

Well Type: OIL UIC Docket No: Date/Time to Plug: 11/03/2000 1:00 PM  
Plug Co. License No.: 5252 Plug Co. Name: NIXON, R P OPERATIONS, INC  
Proposal Rcvd. from: PAUL NIXON Company: NIXON, R P OPERATIONS, INC Phone: (785) 628-3834

Proposed Fluid Level 1200' from surface.  
Plugging Arbuckle completion - open hole 3516' - 3519'.  
Method: Ordered out 325 sxs 60/40 pozmix - 10% gel with 500# hulls.  
No records of squeezing.

Plugging Proposal Received By: HUBERT DEINES WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 11/03/2000 2:40 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perforated salt section at 1850'.  
Anhy. at 1375'. Dakota at 825'.  
Pumped 300 sxs 60/40 pozmix - 10% gel with 500# hulls scattered throughout cement job.  
Max. P.S.I. 800#. S.I.P. 150#.  
Checked backside full fo cement.

RECEIVED  
STATE CORPORATION COMMISSION  
11-15-00  
NOV 15 2000

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed

Richard Williams

(TECHNICIAN)

INVOICED

DATE

11/17/00

FILE NO

2000060994

Form CP-2/3

NOV 08 2000

LEE PHILLIPS

#2

SCHRANDT

4-10-17W

N2 N2 NW

Contr.

ROOKS

Coun

E 2091 RB Comm

Comp

3-2-51

IP

130 BOPD & 18%

PHY POT

WTR

Tops	Depth	Datum
ANH	1348	
TOP	2996	-905
HEEB	3188	-1097
TOR	3211	-1120
LANS	3230	-1139
SIMP	3497	-1406
SIMP SD	3513	-1422
ARB	3516	-1425
T.D.	3519	-1428

Casing

8" 176

ACID 500

5" 3517

SWB 10 BOPH

NETT IE POOL

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS