

15-195-20081-00-00

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name E. H. Adair and Lee Phillips,

Complete Address: Wichita, Kansas. Box 7011

Lease Name Gerstner Well No. 1

Location SW-SW-NE Sec. 21 Twp. 11 Rge. (E) (W) 25

County Trego Total Depth 4048

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Abercrombie Drilling, Incorporated,

Address: 801 Union Center Building, Wichita, Kansas License No.

Operation Completed: Hour 5:30 PM Day 8 Month 8 Year 1968

The Above well was plugged as follows:

215'--8 5/8" Surface pipe, cement circulated with 160 Sx.
Top of Dakota section @ 1240'.

Circulated hole with heavy mud. Pulled DP to 1140' and displaced 100 Sx. cement thru
DP from 1140' to 1115'. Pulled DP to 245' and displaced 20 Sx. cement thru DP from
245' to 185'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

RECEIVED
STATE CORPORATION COMMISSION
8-12-1968
AUG 12 1968
CONSERVATION DIVISION
Wichita, Kansas

Signed: N. L. Nichols
Well Plugging Supervisor

INVOICED
DATE 8/12/68
INV. NO. 8258-W