

15-195-20195-00-00

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
9-21-71
SEP 21 1971
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Benjamin B. Tepper,

Complete Address 420 South Dixie Highway, Coral Gables, Florida.

Lease Name Dechant Well No. 4 *Ver 500*

Location NW-NE-SW Sec. 22 Twp. 11 Rge. (E) (W)25

County Trego Total Depth 4095'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor H-30 Drilling, Incorporated.

Address 200 North Main, Wichita, Kansas. License No.

Operation Completed: Hour 4:00 PM Day 18 Month 9 Year 1971

The above well was plugged as follows:

209'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 900'.

Circulated hole with heavy mud. Pulled DP to 1125' and displaced 100 Sx. cement thru DP from 1125' to 800'. Pulled DP to 240' and displaced 25 Sx. cement thru DP from 240' to 165'. Pulled DP, set bridge @ 40' with $\frac{1}{2}$ sack hulls and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: A. L. Dikels
Well Plugging Supervisor

DATE 9-22-71

INV. NO. 4359-W