

KANSAS

 STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
9-9-1971
SEP 9 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Benjamin B. Tepper,

Complete Address 420 South Dixie Highway, Coral Gables, Florida.

Lease Name Connor Well No. 2

Location NW-SW-SE Sec. 23 Twp. 11 Rge. (E) (W) 25

County Trego Total Depth 3180'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor H-30 Drilling, Incorporated,

Address 200 North Main, Wichita, Kansas. License No.


Operation Completed: Hour 2:30 PM Day 4 Month 9 Year 1971

The above well was plugged as follows:

209'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 875'.

Circulated hole with heavy mud. Pulled DP to 1100' and displaced 100 Sx. cement thru
DP from 1100' to 775'. Pulled DP to 240' and displaced 25 Sx. cement thru DP from
240' to 165'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: 
Well Plugging Supervisor

INVOICED

DATE 9-10-71

INV. NO. 4310-W