

15-195-20155-00-00

Form CP-3  
Rev. 6-4-68

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
APR 21 1970  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Benjamin B. Tepper,

Complete Address 420 South Dixie Highway, Coral Gables, Florida.

Lease Name Connor Well No. 1

Location APP Q E 1/2 E 1/2 NE  
1320' SNL & 440' WEL of Sec. 23 Twp. 11 Rge. (E) (W) 25

County Trego Total Depth 4030'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated     

Plugging Contractor H-30 Drilling, Incorporated,

Address 200 No. Main, Wichita, Kansas. License No.     

Operation Completed: Hour 9:30 PM Day 17 Month 4 Year 1970

The above well was plugged as follows:

208'--8 5/8" Surface casing, cement circulated with 150 Sx.  
Top of Dakota section @ 900'.

Circulated hole with heavy mud. Pulled DP to 1125' and displaced 100 Sx. cement thru  
DP from 1125' to 800'. Pulled DP to 215' and displaced 25 Sx. cement thru DP from  
215' to 140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. Nichols  
Well Plugging Supervisor

INVOICED

DATE 4/21/70

INV. NO. 1758-W