

15-195-20202-00-00

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
FEB 7 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name L. W. Bailey,
Complete Address 200 North Main, Wichita, Kansas.
Lease Name Ziegler Well No. 1
Location E/2-E/2-NE Sec. 27 Twp. 11 Rge. (E) (W) 25
County Trego Total Depth 4030'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor H-30 Drilling, Incorporated,
Address Box #735, Great Bend, Kansas. License No.
Operation Completed: Hour 4:30 AM Day 1 Month 2 Year 1972

The above well was plugged as follows:

268'--8 5/8" Surface casing, cement circulated with 180 Sx.
Top of Dakota section @ 925'.

Circulated hole with heavy mud. Pulled DP to 1150' and displaced 110 Cu. Ft. cement
thru DP from 1150' to 825'. Pulled DP to 275' and displaced 30 Cu. Ft. cement thru
DP from 275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed:

W. L. Nichols
Well Plugging Supervisor

DATE

2/11/72

INV. NO.

5162-W