

15-063-Z0002-00-00

Form CP-3  
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

RECEIVED  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

3-6-1967  
MAR 6 1967

NON-REPLACEMENT  
WICHITA, KANSAS

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Operator's Full Name L. J. Dreiling & Sons, Incorporated.

Complete Address: Victoria, Kansas.

Lease Name Riedel Well No. 1

Location NW-NW Sec. 21 Twp. 11 Rge. (E) (W) 28

County Gove Total Depth 4500

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Above

Address:      License No.     

Operation Completed: Hour 8:00AM Day 2 Month 3 Year 1967

The Above well was plugged as follows:

183'--8 5/8" Surface pipe, cement circulated with 175 Sx.

Circulated hole with heavy mud, set plug @ 600' and displaced 20 Sx.

cement thru DP. Heavy mud to 180', attempted to push plug with 1/4 sack

hulls to 180', plug bridged @ 85', was unable to knock out bridge with

DP. Filled hole from 85' to bottom of cellar using 25 Sx. cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: A. L. Debel

DATE 3/7/67

Well Plugging Supervisor

INV. NO. 4856-W