

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
4-11-1968
APR 11 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Murfin Drilling Company & Koester Assoc.,
Complete Address 617 Union Center Building, Wichita, Kansas.
Lease Name Ziegler Well No. 1
Location CNW-NW Sec. 28 Twp. 11 Rge. (E) (W) 28
County Gove Total Depth 4515'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Murfin Drilling Company,
Address 617 Union Center Building, Wichita, Kansas. License No.
Operation Completed: Hour 3:30 AM Day 7 Month 4 Year 1968

The above well was plugged as follows:

230'--8 5/8" surface casing, cemen circulated with 175 Sx.
Top of Dakota Section @ 1050'.

Circulated hole with heavy mud. Pulled DP to 1275' and displaced 100 Sx. cement thru
DP from 1275' to 950'. Pulled DP to 240' and displaced 20 Sx. cement thru DP from
240' to 180'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. Nichols
Well Plugging Supervisor

DATE 4/11/68

INV. NO. 1563-24