

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION

WELL PLUGGING APPLICATION

Please TYPE Form and File ONE Copy

Form CP-1  
September 2003  
This Form must be Typed  
Form must be Signed  
All blanks must be Filled

API # 15 - 093-00204 - 0000 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date spud 4/17/57

Well Operator: XTO Energy, Inc. KCC License #: 32864

Address: 210 Park Ave., Suite 2350 (Owner / Company Name) City: Oklahoma City (Operator's)

State: OK Zip Code: 73102 Contact Phone: (405) 319 - 3212

Lease: Yates Well #: 1 Sec. 27 Twp. 23 S. R. 38  East  West

C SE Spot Location / QQQQ County: Kearny

1320 Feet (in exact footage) From  North /  South (from nearest outside section corner) Line of Section (Not Lease Line)

1320 Feet (in exact footage) From  East /  West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One:  Oil Well  Gas Well  D&A  Cathodic  Water Supply Well

SWD Docket # \_\_\_\_\_  ENHR Docket # \_\_\_\_\_  Other: \_\_\_\_\_

Conductor Casing Size: N/A Set at: \_\_\_\_\_ Cemented with: \_\_\_\_\_ Sacks

Surface Casing Size: 8 5/8" Set at: 315' Cemented with: 175 Sacks

Production Casing Size: 5 1/2" Set at: 2667' Cemented with: 200 Sacks

Liner Size: 3 1/2" Set at: 2084' w/ tension pkr Cemented with: 120 sacks

List (ALL) Perforations and Bridgeplug Sets: \_\_\_\_\_

Sqz perfs @ 2618', sqz'd w/ 200 sx cmt. Production perfs @ 2586'-2602' & 2634'-2650'

Elevation: 3329 ( G.L. /  K.B.) T.D.: 2668' P.B.T.D.: 2667' Anhydrite Depth: +/- 2036'

(Stone Corral Formation)

Condition of Well:  Good  Poor  Casing Leak  Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Pump a 50'+ cmt plug 2585'-2535', pump a 100'+ cmt

plug 2134'-2034', pump 100'+ cmt plug (in & out) 365'-265, pump 30' cmt plug from 34' to 4'. Mud (9 ppg min.) will be pumped

between each cmt plug.

Is Well Log attached to this application as required?  Yes  No Is ACO-1 filed?  Yes  No

If not explain why? No ACO-1 available.

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: David Littell or Mark Gosch

Phone: (620) 355 - 7838

Address: 805 S. Hwy 25 City / State: Lakin, KS 67860

Plugging Contractor: Not selected at this time KCC License #: \_\_\_\_\_ (Contractor's)

Address: \_\_\_\_\_ Phone: ( ) - \_\_\_\_\_

Proposed Date and Hour of Plugging (if known?): Not known at this time

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 5/7/09 Authorized Operator / Agent: Karen Byers (Signature)

KANSAS CORPORATION COMMISSION

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

MAY 11 2009

RECEIVED

*Handwritten signature/initials*



CORPORATION COMMISSION

Mark Parkinson, Governor Thomas E. Wright, Chairman Michael C. Moffet, Commissioner Joseph F. Harkins, Commissioner

**NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)**

XTO ENERGY INC.  
210 PARK AVE STE 2350  
OKLAHOMA CITY, OK 73102-5683

May 13, 2009

Re: YATES #1  
API 15-093-00204-00-00  
27-23S-38W, 1320 FSL 1320 FEL  
KEARNY COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

**This notice is void after November 9, 2009. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.**

Sincerely,

Steve Bond  
Production Department Supervisor

District: #1  
210 E Frontview, Suite A  
Dodge City, KS 67801  
(620) 225-8888