

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-165-21846-00-00  
Spot: NENENENW Sec/Twnshp/Rge: 20-18S-19W  
90 feet from N Section Line, 2570 feet from W Section Line  
Lease Name: KELLER UNIT Well #: 1-20  
County: RUSH Total Vertical Depth: 4070 feet

Operator License No.: 9855  
Op Name: GRAND MESA OPERATING COMPANY  
Address: 1700 N WATERFRONT PKWY BLDG 600  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	1241		WITH 450 SX CMT
PROD	5.5	4067	2230	WITH 185 SX CMT

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/20/2009 8:30 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SAND TO 3875' & 5 SX CMT. PLUG AT 1270' WITH 15 SX GEL & 50 SX CMT. PLUG AT 600' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

132.28

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 04/20/2009 3:20 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

PUMP 30 SX CMT W/200# HULLS. DISPLACED TO 3500'. MAXIMUM PRESSURE = 1800 PSIG. SPOTTED PLUGS THROUGH CASING WHILE PULLING. 1ST PLUG AT 1260' WITH 15 SX GEL - 50 SX CMT. 2ND PLUG AT 600' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4002	4005		
3936	3941		
3928	3932		

INVOICED

DATE 5-12-09  
INV. NO. 2009061538

KANSAS CORPORATION COMMISSION  
MAY 01 2009  
RECEIVED

Remarks: USED CLASS C W/3% CC BY QUALITY OIL WELL CEMENTING.

Plugged through: CSG

District: 01

RECEIVED  
APR 24 2009  
KCC DODGE CITY

Signed Richard W. Lacey  
(TECHNICIAN)