

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-20287-00-01  
Spot: NESWNE Sec/Twnshp/Rge: 33-15S-20W  
3637 feet from S Section Line, 1718 feet from E Section Line  
Lease Name: STEPHANS Well #: 1-A  
County: ELLIS Total Vertical Depth: 3938 feet

Operator License No.: 33786  
Op Name: DOUBLE D'S LLC  
Address: 133 E 12TH  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	225	0	155 SX CMT.
T1	2.875	3922		
PROD	5.5	3932	0	500 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/29/2009 12:00 PM  
Plug Co. License No.: 32528 Plug Co. Name: FUNK, DAVID A. DBA OIL AND OPERATING SERVICES  
Proposal Rcvd. from: DUANE BIEKER Company: DOUBLE D'S LLC Phone: (785) 230-0113

Proposed Plugging Method: Ordered 450 sxs 60/40 pozmix - 4% gel - 500# hulls.  
5 1/2" cemented bottom to surface with 500 sxs.

127.99

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 04/29/2009 2:45 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 1900'.  
Quality Oil Well Cementing pumped 195 sxs 60/40 pozmix - 4% gel with 300# hulls.  
Lost circulation.  
Pulled to 800' - pumped 200 sxs cement with 100# hulls cwc.  
PTOH. Squeezed 5 1/2" casing with 55 sxs cement with 100# hulls.  
Max. P.S.I. 400#. S.I.P. 200#  
Backside instant pressure.

Perfs:

Top	Bot	Thru	Comments
3932	3938		

INVOICED  
DATE 5-12-09  
INV. NO. 2009061543

KANSAS CORPORATION COMMISSION  
MAY 04 2009

Remarks: QUALITY OILWELL CEMENTING COMPANY.

RECEIVED

Plugged through: TBG

District: 04

Signed Richard Williams  
(TECHNICIAN)

CM

Form CP-2/3

APR 30 2009

DOUBLE D'S LLC  
HAYS KS 67601

33-15S-20W  
NE SW NE  
KANSAS

#1-A STEPHANS OWWO

City: ELLIS Spot: C NE SW NE API 15-051-20287  
Site: 15-1/4 S & 1/4 E OF ELLIS KS Lat/Long: 38.70661 -99.54825  
Field: WALLACE  
FR: 04/03/2007 Spd: 09/19/2007 Drfg Cp: 09/21/2007 Issued: 12/10/2007 Revised: 12/10/2007


Copyright 2007 Independent Oil & Gas Service, Inc. Wichita, KS

Side 1

**IP Status:**  
OIL, P 3 BOPD & WTR, CONG 3932-3938, 11/1/2007  
Contr: ULTIMATE WELL SVC  
Elev: 2238 KB  
Formation Tops: (L-Log, S-Sample, D-Driller)

*SAMPLE TOP	
L ANH	1489 +769
L B/ANH	1515 +723
S TOP	3226 -988
L HEEB	3504 -1266
L LANS	3548 -1310
L BKC	3802 -1564
L MARM	3869 -1631
S PAW	3872 -1634
L CONG SH	3924 -1686
CONG SD	3930 -1692
RTD OLD	3933 -1695
LTD OLD	3935 -1697
DDTD OLD	3938 -1700

**Old Info:**  
Well Record: RAINS & WILLIAMSON OIL CO. #2  
STEPHENS A, SPD 07/14/1968, DC 07/21/1968,  
8-5/8" 225 / 155 SX (ALT 2), 5-1/2" 3932 / 150 SX,  
OIL, P 168 BOPD, NW, CONG 3932-3938,  
9/3/1968(CARD ISSUED 09/05/1968)  
Contr: RAINS & WILLIAMSON  
Geol: HAROLD L. STEINCAMP  
Finds:  
SHOWS: 3624-3632 (LKC LM, FR VUG PORO,  
10% STND), 3650-3654 (LKC LM, PR PNPT  
PORO, SCAT STN), 3930-3933 (CONG SD,  
MED-CRSE GRN, CLR, FRIA, FSFO, NO ODOR,  
FEW CLSTRS, SME LSE SD GRNS)  
NO CORES  
DST(1) 3923-3933 (CONG SD) 15-30-60-30, WB  
BLT TO SB, REC 630' TF: 510' CLEAN OIL, 120'  
HOCM ISIP 1047# FSIP 975# IFP 105# / FFP 222#  
BHT 115'

DOUBLE D'S LLC  
HAYS KS 67601

33-15S-20W  
NE SW NE  
KANSAS  
Side 2

#1-A STEPHANS OWWO

Copyright 2007 Independent Oil & Gas Service, Inc. Wichita, KS

**Comp Info:** MICT - CO TO 3933, (CONG SD OH),  
FU 500' OIL/12 HRS, NAT, SWB 0.75 BOPH, NW,  
DD 3937, NO INCR, FU 600' OIL, NW/12 HRS,  
SWB 0.75 BOPH, DD 3938 TD, FU 2830' OIL,  
NW/12 HRS, (GR 35.9), POP, P 147 BO, NW/24  
HRS, IPP 168 BOPD, NW, 9/3/1968; STATE TEST:  
P 176 BOPD, NW

**New Info:**  
Well Record: FR 04/03/2007, RE-ENTERED  
09/19/2007, WSH DWN TO 3938, DC 09/21/2007,  
PROD CSG ALREADY IN HOLE

**Finds:**  
COMMENT: PROPOSED START 5/15/2007; KCC  
API 15-051-20287-0001

**Comp Info:** TRGT ZN: CONG SD (OIL), PTD 3938  
(CONG), MICT - CO, (CONG SD OH), SWB DWN,  
SO, POP, P 3 BOPD & WTR, 11/1/2007.