

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-063-20,702-00-00
_____, Sec. 3, T 11 S, R 27 (W/E)
350' feet from (N) section line
1650' feet from (W) section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9123
Operator: Diamond Shamrock
Name & Address: P.O. Box 631
Amarillo, Texas
79173

Lease Name Ochs-Zee Well # 38-3
County Tove
Well Total Depth 4750 feet 154.38
Conductor Pipe: Size - feet -
Surface Casing: Size 8 5/8 feet 300' w/235

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Abercrombie Drlg License Number Rig I
Address (Pete Coates) - Wichita, Kansas

Company to plug at: Hour: 10:00 A Day: 22 Month: 2 Year: 1984

VERBAL PLUGGING ORDERS GIVEN TO Pete Coates

(company name) Abercrombie Drlg. (phone) _____

were: Elev - 2674' only - 2256 arb - yes

Ordered 200 sy. 5 1/2 poz, 6% gel, 3% CC, 1 sy bulls +
8 5/8" w. plug

Circulate heavy mud between all plugs.

Signed Dennis L. Hamel
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 12:00 A Day: 22 Month: 2 Year: 1984

ACTUAL PLUGGING REPORT

Spotted 20 sy @ 4700' ; Spotted 20 sy @ 2260'
" 100 sy @ 1275' (w/1 sy bulls)
" 40 sy @ 310'
" 10 sy @ 40'-0 (solid bridge)
" 10 sy in Rat Hole

Remarks: _____

RECEIVED
STATE CORPORATION COMMISSION
3-12-1984
MAR 12 1984

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated
and that I (did did not) observe this plugging.

Signed Dennis L. Hamel
(TECHNICIAN)

INVOICED
DATE 3-13-84
INV. NO. 0720