

2-5 4-061045

15-063-21498-00-00

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-063-21,498-00-00

SW SW NE /4 SEC. 05, 11 S, 28 W
2970 feet from S section line
2310 feet from E section line

Operator license# 9860

Lease Hartman Well # 1

Operator: Castle Resources, Inc.

County: Gove 147.87

Address: 1200 East 27th Street - #C
Hays, Kansas 67601

Well total depth 4550 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 209 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Discovery Drilling, Inc. License# 31548

Address: Hays, Kansas 67601

Company to plug at: Hour: 5:00 P.M. Day: 5 Month: February Year: 1997

Plugging proposal received from: Tom Alm

Company: Discovery Drilling, Inc. Phone: _____

Were: Order 200 sxs 60/40 posmix - 6% gel with 1/4# floseal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All[], Part[], None[]

Completed: Hour: 7:30 P.M., Day: 5, Month: February, Year: 1997

Actual plugging report: _____

1st. Plug at 2365' w/25 sxs. Anhydrite 2347' - 2380'.

2nd. Plug at 1400' w/100 sxs. Dakota 1092' - 1392'.

3rd. Plug at 260' w/40 sxs. Surface pipe at 209'.

4th. Plug at 40' w/10 sxs.

15 sxs in rathole.

10 sxs in mousehole.

RECEIVED
STATE CORPORATION COMMISSION
2-11-1997
FEB 11 1997

Remarks: Allied Cementing.


CONSERVATION DIVISION
Wichita, Kansas

Condition of casing(in hole): GOOD BAD _____ Anhy.plug: YES NO _____

Bottom plug(in place): YES _____, CALC _____, NO Dakota plug: YES NO _____

Plugged through TUBING _____, CASING _____. Elevation: 2792 GL

I did[] / did not[] observe the plugging.



(agent)

Form CP-2/3

INVOICED

DATE FEB 13 1997

INV. NO. 47572

2-5