

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-25859-00-00
Spot: W2E2NW Sec/Twnshp/Rge: 36-13S-18W
1270 feet from N Section Line, 1600 feet from W Section Line
Lease Name: BRAUN Well #: 1
County: ELLIS Total Vertical Depth: 3650 feet

Operator License No.: 33625
Op Name: HERTEL OIL COMPANY LLC
Address: 704 E 12TH ST
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	222		

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 03/29/2009 3:45 AM
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING
Proposal Rcvd. from: TOM ALM Company: HERTEL OIL COMPANY LLC Phone: (785) 628-2445

Proposed Plugging Method: Ordered 245 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

118.63

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: NONE
Date/Time Plugging Completed: 03/29/2009 8:15 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

1st. Plug at 3600' w/25 sxs.
2nd. Plug at 1290' w/25 sxs.
3rd. Plug at 730' w/100 sxs.
4th. Plug at 275' w/40 sxs.
5th. Plug at 40' w/10 sxs.
Rathole with 30 sxs.
Mousehole with 15 sxs.

Perfs:

INVOICED

DATE 5-13-09
INV. NO. 2009061546

KANSAS CORPORATION COMMISSION

MAY 04 2009

RECEIVED

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed

R. Williams

(TECHNICIAN)

CM

Form CP-2/3

PKT

MAY 01 2009