

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-055-21467-00-00
Spot: NENENWSE Sec/Twnshp/Rge: 10-25S-31W
2500 feet from S Section Line, 1600 feet from E Section Line
Lease Name: TANCAYO Well #: 1-10
County: FINNEY Total Vertical Depth: 2635 feet

Operator License No.: 9152
Op Name: MAREXCO, INC.
Address: 3033 NW 63RD ST - STE 151
OKLAHOMA CITY, OK 73116

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	335		WITH 230 SX CMT
PROD	4.5	2631	0	WITH 575 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/21/2009 9:30 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: RODNEY GONZALES Company: MAREXCO Phone: (405) 286-5657

Proposed Plugging Method: STOPPED PRODUCING ECONOMICALLY AS PER STEVE DURRANT; DIG OUT CELLAR, PILL SPACER, 200# COTTON SEED HULLS, 25 SX CEMENT GELL SPACER UP TO 1050' FILL W/ 225 SX CEMENT TO SURFACE CHECK ANNULUS W/50 SX CMT

85.64

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/21/2009 11:30 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

FILL 4 1/2" CASING FROM 2597' - 0' USING 350# HULLS & 225 SX CMT. PRESSURE TO 400# & HELD. PUMP 20 SX CMT DOWN 4 1/2" X 8 5/8" ANNULUS. PRESSURE TO 300# & HELD.

Perfs:

Top	Bot	Thru	Comments
2587	2597		4 SHOTS/FOOT

KANSAS CORPORATION COMMISSION

MAY 06 2009
RECEIVED

INVOICED

DATE 5-13-09
INV. NO. 2009061550

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG


District: 01

RECEIVED

APR 23 2009

KCC DODGE CITY

Signed



(TECHNICIAN)

Form C-2/3

PRT