

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-081-21203-00-00
Spot: NENW Sec/Twnshp/Rge: 23-30S-34W
660 feet from N Section Line, 1980 feet from W Section Line
Lease Name: SCHNELLBACHER TRUST Well #: 1-323
County: HASKELL Total Vertical Depth: 5600 feet

Operator License No.: 8061
Op Name: OIL PRODUCERS INC. OF KANSAS
Address: 1710 WATERFRONT PKWY
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4500		WITH 2 SX CMT
SURF	8.625	1667		WITH 550 SX CMT
PROD	4.5	4972	1730	WITH 150 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/09/2009 3:00 PM
Plug Co. License No.: 34091 Plug Co. Name: BLACKHAWK WELL SERVICE, LLC
Proposal Rcvd. from: BARRY WALTERS Company: BLACKHAWK WELL SERVICE, LL Phone: (785) 623-1066

Proposed Plugging Method: CIBP @ 4500' & 2 SX CMT. LOAD HOLE WITH GEL WATER. PLUG AT 1690' WITH 50 SX CMT. PLUG AT 660' WITH 50 SX CMT. PLUG AT 40-0' WITH 10 SX CMT.
182.00

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/09/2009 6:00 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

CIBP @ 4500' WITH 2 SX CMT. 1ST PLUG AT 1700' WITH 50 SX CMT. 2ND PLUG AT 660' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4729	4735		MARMATON
4539	4545		KANSAS CITY

KANSAS CORPORATION COMMISSION
MAY 01 2009
RECEIVED

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.
Plugged through: TBG

INVOICED
DATE 5-13-09
INV. NO. 2009061552

District: 01

RECEIVED
APR 15 2009
KCC DODGE CITY

Signed Jack MacLaskey
(TECHNICIAN)